

University Leipzig
Institute for Biochemistry &
Institute for Earth System Science and Remote Sensing
B.Sc. Biochemistry &
B.Sc. Geography



BACHELOR THESIS

Physiological and geodata analyses of methane reduction potential in ruminants

Submitted by: Linus Benetz
Matriculation number: 37807522

Supervisors: Professor Bastian Molitor
Professor Ana Bastos

Handed in: 15.09.2026

ABSTRACT

Methane is the second most abundant greenhouse gas in the atmosphere (1935 ppb) after CO₂ (423 ppm) and is responsible for around 30 % (gross) of anthropogenic global temperature rise. Because of its high global warming potential, especially on a short time period, methane is an excellent target for mitigation. Right now, methane is still accumulating globally in the atmosphere through the emission of mainly three sectors: energy, waste and agriculture. While the emission from the energy and the waste sector could be reduced with established technologies easily, the agriculture sector is classified as "hard-to-abate". This bachelor thesis investigates one possible mitigation strategy to solve this: the "immunization of cattle". For this purpose, a more holistic approach was chosen, combining a biochemistry and a geography part.

In the biochemistry part, I performed a microbiological investigation of *Methanobrevibacter* as the dominant rumen archaea, which are the biological entities that generate methane in the digestive tract of ruminants. The goal was to achieve DNA transfer in *Methanobrevibacter*, which has not been demonstrated before. Thereby, the focus was primarily on two species (*Methanobrevibacter thaueri* CW^T and *Methanobrevibacter boviskoreani* AbM4). It was shown that the species can be cultivated in pure culture in liquid and solid media and are sensitive to puromycin and DMSO. Furthermore, promising results were achieved to transform these species for the first time via interdomain conjugation with *Escherichia coli*, but verification via whole-genome sequencing is still pending. In the future, the established genetic tool can help to identify a specific and potent vaccine that targets only the anaerobic, methanogenic archaea in the rumen of cattle. The long-time goal is to shift the microbiome towards more non-methanogenic microbes, such as acetogenic bacteria, so that the digestive efficiency of cattle is not compromised.

In the geographical part, I tried to evaluate the potential role of the investigated mitigation strategy to slow down climate change. For this purpose, the changed methane emission from enteric fermentation processes in cattle were calculated for different success scenarios of microbiome shift for three countries (Germany, New Zealand, USA) and its impact on national CH₄ emission. The calculation is based on the 2006 published guidelines by the IPCC. The geodata analyses showed for a shift of at least 30 % a relevant impact to achieve international emission targets. Given the current state of vaccine development, this method cannot play a significant role in reducing emissions over the next decade. However, in the long term, the technology could offer a solution that allows for a sustainable cattle population size that is socially and politically acceptable, even though a reduction will likely still be necessary.

Future research should further develop genetic tools to intensify the investigation of methanogenic archaea. Additionally, it should be assessed whether immunization of cattle could affect emissions beyond enteric methane, either amplifying or offsetting the overall emission reduction potential.

CONTENTS

LIST OF FIGURES	VII
LIST OF TABLES	X
LIST OF ABBREVIATIONS	XI
1 INTRODUCTION	1
1.1 Methane production in cattle farming and a possible mitigation	3
1.2 Evaluation based on calculated CH ₄ emission	5
2 DATA AND MATERIALS	7
2.1 Biochemistry	7
2.1.1 Organism	7
2.1.2 Chemicals	7
2.1.3 Materials	8
2.2 Geography	8
2.2.1 Study area	8
2.2.2 CRT Data	9
2.2.3 Reference data	10
2.3 Software	10
3 METHODS	12
3.1 Biochemistry	12
3.1.1 Liquid media preparation for <i>Methanobrevibacter</i>	12
3.1.2 Solid media preparation for <i>Methanobrevibacter</i>	13
3.1.3 Cell counting	14
3.1.4 Sensitivity experiments	15
3.1.5 Plasmid construction	15
3.1.6 Transformation of <i>Methanobrevibacter</i>	17
3.1.7 Ethanol as alternative substrate	20
3.2 Geography	20
3.2.1 Processing CRT-Data	20
3.2.2 Calculation of methane emissions from enteric fermentation processes in cattle	21
3.2.3 Share of cattle methane emissions from enteric fermentation	21

3.2.4	Calculation of saved methane	21
3.2.5	Prediction of CH ₄ emission until 2030	24
4	RESULTS	26
4.1	Biochemistry	26
4.1.1	Cultivation	26
4.1.2	Cell count	27
4.1.3	Plating	28
4.1.4	Antibiotic sensitivity	30
4.1.5	Nucleotide-baseanalogica sensitivity test	33
4.1.6	<i>pac</i> -gene	38
4.1.7	Transformation via conjugation	39
4.2	Geography	41
4.2.1	National methane emission since 1990	41
4.2.2	Enteric fermentation processes of cattle	43
4.2.3	Reductionpotential in enteric fermentation processes of cattle	46
4.2.4	Prediction for 2030	47
5	DISCUSSION	54
5.1	Biochemistry	54
5.1.1	Transformation via conjugation	54
5.1.2	Plasmid constructs	55
5.1.3	Sensitivity tests	56
5.1.4	General characterization of <i>Methanobrevibacter</i>	58
5.2	Geography	60
5.2.1	Evaluation of immunization of cattle" as a mitigation strategy	60
5.2.2	Characterization of national emission	63
5.2.3	Future steps	65
6	CONCLUSION	67
	ACKNOWLEDGEMENTS	71
	BIOCHEMICAL TERMS	73
	GEOGRAPHICAL TERMS	77
	REFERENCES	81

APPENDIX	i
A Figures	i
B Tables	iv
DECLARATION	

LIST OF FIGURES

1	The share of the three main GHG (CO ₂ , CH ₄ , N ₂ O) on the anthropogenic temperature rise since 1850.	1
2	Sketch of the general structure of the suicide plasmids for the transformation of <i>Methanobrevibacter thaueri</i> CW ^T and <i>Methanobrevibacter boviskoreani</i> AbM4 via conjugation using <i>E. coli</i>	5
3	Suicide plasmid maps for transformation by conjugation for <i>M. thaueri</i> and <i>M. boviskoreani</i>	16
4	Methodological approach to transform a <i>Methanobrevibacter</i> species via inter-domain conjugation using two diaminopimelic acid (DAP) auxotrophic <i>E. coli</i> strains, WM6026 and WM6029.	18
5	Spread plating results of <i>M. thaueri</i> and <i>M. boviskoreani</i>	28
6	Roll plating of <i>M. thaueri</i> , <i>M. wolinii</i> and <i>M. boviskoreani</i> in 10 mL DSM 1523 (1.5 % agar).	29
7	Growth curve in DSM 1523 for <i>M. boviskoreani</i> for various concentration of puromycin (Puro): 0 µg/mL, 1 µg/mL, 2 µg/mL, 5 µg/mL, 10 µg/mL and 20 µg/mL.	31
8	Growth curve in DSM 1523 for <i>M. thaueri</i> for various concentration of puromycin (Puro): 0 µg/mL, 1 µg/mL, 2 µg/mL, 5 µg/mL, 10 µg/mL and 20 µg/mL.	32
9	Growth curve in DSM 1523 for <i>M. boviskoreani</i> for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) and one bottle with 1 mL DMSO as solvent of 8-Aza.	34
10	Growth curve of <i>M. thaueri</i> for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) in DSM 1523 and one bottle with 1 mL DMSO as solvent of 8-Aza.	35
11	Growth curve of <i>M. millerae</i> for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) in DSM 1523 and one bottle with 1 mL DMSO as solvent of 8-Aza.	36
12	Color differences with and without DMSO after 6 days of incubation.	37
13	Aminoacids (AA) sequence of two <i>pac</i> genes and their 3-D structures.	38
14	Gel image for different PCR products of growing cultures of <i>M. boviskoreani</i> and <i>M. millerae</i> after conjugation.	40
15	Time series of the anthropogenic methane emission of Germany (DEU), New Zealand (NZL) and United States of America (USA).	41

16	Time series of methane emission derived from enteric fermentation processes in cattle and its subcategories dairy and non-dairy for the countries: Germany (DEU), New Zealand (NZL) and United States of America (USA).	43
17	Time series of the share of methane emissions resulting from enteric fermentation of cattle on methane produced in the entire agriculture sector and the total amount of CH ₄ per country and year.	45
18	Saved CH ₄ through different scenarios (10, 20, 30, 40 and 50 %) of a successful shift of rumen microbiome towards non-methanogenic microbes.	47
19	Historical values for total methane emissions in Tg for Germany from 1990 to 2024 and the forecast of methane emissions through 2030.	48
20	Historical values for total methane emissions in Tg for New Zealand from 1990 to 2024 and the forecast of methane emissions through 2030.	50
21	Historical values for total methane emissions in Tg for the USA from 1990 to 2022 and the forecast of methane emissions through 2030.	51
A1	Phase-contrast microscope picture of <i>Methanobrevibacter boviskoreani</i> AbM4 culture precipitate at 1000 times magnification.	i
A2	Phase-contrast microscope picture of <i>Methanobrevibacter boviskoreani</i> AbM4 at 400 times magnification.	i
A3	Pour plating result of <i>Methanobrevibacter thaueri</i> CW ^T DSM 119 (1 % agar).	ii
A4	Time series of methane conversion factor (Y _m), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for Germany.	ii
A5	Time series of methane conversion factor (Y _m), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for New Zealand.	iii
A6	Time series of methane conversion factor (Y _m), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for United States of America.	iii

LIST OF TABLES

2	Composition of the starting solution for the preparation of DSM 1523.	12
3	Composition of the starting solution for the preparation of DSM 119.	12
4	Cellnumber per mL of different <i>Methanobrevibacter</i> (<i>Methanob.</i>) culture for corresponding optical density at 600 nm (OD600).	27
5	Counted colony forming unit (CFU) and estimated plating efficiency of different <i>Methanobrevibacter</i> (<i>Methanob.</i>) cultures for the roll plating technique.	30
B1	Composition for the solution A as a part of the DSM 1523 and DSM 119. . . .	iv
B2	Composition for the solution B as a part of the DSM 1523.	iv
B3	Composition for the trace element solution SL-10 as a part of the DSM 1523 and DSM 119.	iv
B4	Composition for the seven vitamins solution as a part of the DSM 1523. . . .	v
B5	Composition for the fatty acid mixture as a part of the DSM 119.	v
B6	Composition for the FeSO₄ x 7 H₂O solution (0.1 % w/v) as a part of the DSM 119.	v
B7	Primerlist of the primers used in this bachelor thesis. Besides the name of the primer, also the sequence (5' to 3') is given and its annealing temperature (T _a) with the Q5- and OneTaq-DNA-polymerase.	vi
B8	Counted cells for <i>Methanobrevibacter wolinii</i> SH ^T with an OD600 of 0.387. . .	vii
B9	Counted cells for <i>Methanobrevibacter wolinii</i> SH ^T with an OD600 of 0.396. . .	vii
B10	Counted cells for <i>Methanobrevibacter thaueri</i> CW ^T with an OD600 of 0.235. . .	vii
B11	Counted cells for <i>Methanobrevibacter thaueri</i> CW ^T with an OD600 of 0.116. . .	viii
B12	Counted cells for <i>Methanobrevibacter millerae</i> SM9 with an OD600 of 0.378. .	viii
B13	Counted cells for <i>Methanobrevibacter boviskoreani</i> AbM4 with an OD600 of 0.287.	viii
B14	The total average of counted cells (ø cellnumber) for each <i>Methanobrevibacter</i> (<i>Methanob.</i>) culture with corresponding OD600.	viii
B15	In-silico produced suicide plasmid constructs for transformation of <i>Methanobrevibacter thaueri</i> CW ^T and <i>Methanobrevibacter boviskoreani</i> AbM4 via conjugation.	ix
B16	Preparation of the conjugation for the transformation of <i>Methanobrevibacter thaueri</i> CW ^T , <i>Methanobrevibacter boviskoreani</i> AbM4, and <i>Methanobrevibacter millerae</i> SM9.	x

B17	Lists saved CH ₄ for five scenarios of different success in shifting the microbiom from methanogen towards non-methanogen (10, 20, 30, 40 and 50 %).	xi
B18	Listed linear models for predicting relevant values for calculating 2030 CH ₄ emission of Germany	xii
B19	Listed linear models for predicting relevant values for calculating 2030 CH ₄ emission of New Zealand	xiii
B20	Listed linear models for predicting relevant values for calculating 2030 CH ₄ emission of the USA	xiv

LIST OF ABBREVIATIONS

CO ₂ -eq.	CO ₂ equivalent.
<i>hpt</i>	hypoxanthine phosphoribosyltransferase.
8-Aza	8-Azahypoxanthin.
AA	aminoacids.
AB	antibiotic.
bp	base pairs.
CAP	chloramphenicol.
CFU	colony forming unit.
CI	confidence intervall.
CoM	coenzyme M.
CRT	common reporting table.
Cyc-Se.	cycloserin.
DAP	diaminopimelic acid.
DC	dairy cattle.
DE	digestibility of food.
DEU	Germany.
DMSO	dimethylsulfoxid.
DTT	dithiothreitol.
EF	emission factor.
EnterFe	enteric fermentation.
eq.	equivalent.
<i>E. coli</i>	<i>Escherichia coli</i> .
<i>E. coli</i> DH5 α	<i>Escherichia coli</i> DH5 α .
<i>E. coli</i> WM6026	<i>Escherichia coli</i> WM6026.
<i>E. coli</i> WM6029	<i>Escherichia coli</i> WM6029.
EtOH	ethanol.

gDNA	genomic DNA.
GDP	gross domestic product.
GE	gross energy intake.
GHG	greenhouse gas.
GMP	global methane pledge.
GWP	global warming potential.
IPCC	intergovernmental panel on climate change.
LULUCF	land use and land use change and forestry.
<i>M. boviskoreani</i>	<i>Methanobrevibacter boviskoreani</i> AbM4.
<i>Methanob.</i>	<i>Methanobrevibacter.</i>
MIC	minimum inhibitory concentration.
<i>M. millerae</i>	<i>Methanobrevibacter millerae</i> SM9.
<i>M. thaueri</i>	<i>Methanobrevibacter thaueri</i> CW ^T .
<i>M. wolinii</i>	<i>Methanobrevibacter wolinii</i> SH ^T .
NDC	non-dairy cattle.
NZL	New Zealand.
OD600	optical density at 600 nm.
OECD	organisation for economic co-operation and development.
PB	planetary boundaries.
Puro	puromycin.
rRNA	ribosomal RNA.
rRNA	ribosomal RNA.
Sqr.	square.
ss-DNA	singlestranded-DNA.
<i>S. epidermidis</i>	<i>Staphylococcus epidermidis</i> .

UNFCCC	united nations framework convention on climate change.
USA	United States of America.
Ym	methane conversion factor.

1 INTRODUCTION

The pressing situation of the planets "health" is a scientific consensus (IPCC, 2022b; Planetary Boundaries Science (PBScience), 2025). We can already see the negative impact in our day to day live that the taken projectories over the last decades are to be proven true, so a temperature rise in Europe of 2.5 °C towards preindustrial times can be measured as well as a higher frequency of compound events (C3S/ECMWF & WMO, 2026; Ionita & Nagavciuc, 2026). This led to an extreme heat wave this summer (2026) in Europe, which, in Germany alone, is estimated to have resulted in more than 14 000 deaths (RKI, 2026). Therefore, it is highly necessary to develop strategies for adaption to this changing environment, but more so for mitigation to stabilize the climate and to keep at least the 2 °C goal of the Paris Agreement (UNFCCC, 2015).

One of the main drivers for this development is the anthropogenic-induced climate change. Climate is one of nine earth systems processes (Climate Change, Biosphere Integrity, Land System Change, Freshwater Change, Biogeochemical Flows, Ocean Acidification, Atmospheric Aerosols Loading, Stratospheric Ozone, Novel Entities) that are relevant for containing a stable system on earth, to grant condition, in which mankind can knowingly thrive (Planetary Boundaries Science (PBScience), 2025). Like six other of them, climate change exceeded its planetary boundaries (PB) already (ibid.). Just Atmospheric Aerosols Loading, Stratospheric Ozone are within their PB.

The relevant value for climate change is the anthropogenic radiative forcing, which not only exceeded the PB ($+1 \text{ W/m}^2$) 2025 but the boundary for the zone of an increasing risk ($+1.5 \text{ W/m}^2$) as well with a value of 2.97 W/m^2 (Irfan et al., 2024; Planetary Boundaries Science (PBScience), 2025, p.13). Figure 1 shows the impact of this on global temperature since the industrial revolution, with an increase of just under 1.7 °C. It also shows how much of this increase is caused by each of the three most important anthropogenic greenhouse gas (GHG) -CO₂, CH₄, and N₂O - broken down by emission source ("Fossil Fuels and Industry" or "Agriculture and Land"). Nitrous dioxide has a minor impact and is responsible for a total of




Figure 1: The share of the three main GHG (CO₂, CH₄, N₂O) on the anthropogenic temperature rise since 1850. Each GHG is subdivided in two groups depending on the emission source ("Agriculture and Land" or "Fossil and Industry"). Source: (Planetary Boundaries Science (PBScience), 2025), licensed under CC BY 4.0

approximately 0.1 °C. CO₂, on the other hand, has the biggest responsibility for the temperature rise (more than 50 %, Figure 1) due to its high abundance in the atmosphere (423 ppm in 2025) (GML, 2025; Planetary Boundaries Science (PBScience), 2025).

The second most abundant GHG is methane, with the biggest relative increase in atmospheric concentration of around 265 % from 720 ppb 1750 to 1935 ppb in 2026 (Appelhans et al., 2025; Planetary Boundaries Science (PBScience), 2025; Thoning et al., 2022). Methane is also responsible (Figure 1) for around 30 % (gross) of the anthropogenic temperature rise (Appelhans et al., 2025, p. 9). If compared to CO₂ some features makes it highly interesting as a potential target for mitigation. The stronger impact of methane on radiative forcing and its relatively short lifetime in the atmosphere of 12.4 years (15-40 % of CO₂ is still in the atmosphere after 1000 years) (Appelhans et al., 2025) lead to global warming potential (GWP) values that strongly decline over longer time horizons (GWP20: 79.7 and GWP100: 27 for non-fossil CH₄ in IPCC (2023a, Table 7.15)).

This means that, as a mitigation strategy addressing CH₄, reducing methane emissions is sufficient to achieve a notable impact within two decades, whereas mitigation strategies for CO₂ must also focus on the removal of CO₂ from the atmosphere. Because of that, international initiatives aim at reducing methane emissions such as the global methane pledge (GMP), which was initiated in 2021 and signed by 160 states including Germany (DEU), New Zealand (NZL) and United States of America (USA) (CCAC, n.d.). The participants commit to emit 30 % less methane than they did in 2020 and 40 % less than in 2010, without any penalties (Appelhans et al., 2025).

However, right now methane is still accumulating in the atmosphere (Saunois et al., 2025; Thoning et al., 2022). Globally the three biggest sources for anthropogenic CH₄ are the agriculture- (approx 40 %), energy- (36 %) and waste-sector (22 %) (Appelhans et al., 2025; Mundra & Lockley, 2024). The emissions derived from the energy and waste sectors can be substantially reduced using existing technical knowledge and available mitigation options (Appelhans et al., 2025; IPCC, 2022a). Emissions from agriculture, on the other hand, are counted as "hard-to-abate", because the world is lacking technologies and strategies that are socially and political accepted (Edelenbosch et al., 2024; IPCC, 2022a; Thoning et al., 2022). This is due to the fact that methane arises naturally in agriculture from biological processes, primarily through enteric fermentation, especially in cattle (77 %), and manure management. Together they make up for 31 % of global methane emission (Appelhans et al., 2025; Smith et al., 2021). The only option for reducing methane emissions for this right now is to reduce the

number of live stock dramatically, which is contrary to the global rise of demand for livestock products and globally rising numbers of livestock (Edelenbosch et al., 2024; FAO, 2009).

This bachelor thesis wants to tackle this lack of options by further investigating a mitigation strategy for the largest single source of methane emissions in the agricultural sector: "immunization of cattle" against its methanogenic microbiome in the rumen. For this purpose, an interdisciplinary approach was chosen with a biochemical and geographical part, which allows uniting two scales of investigation in one work.

The biochemistry part investigates new approaches to reduce methane production on cellular or organism level, while the geographical part places the results in the context of multifactorial climate change and assess the extent to which the biochemical approach can play a role to mitigate.

1.1 Methane production in cattle farming and a possible mitigation

Cattle as a ruminant has a rumen which enables them to break down and digest long fibers of carbohydrates such as plant cells via microbial fermentation (EPA, 2024; Moss et al., 2000). These fermentation processes carried out by a wide variety of microbes produce H_2 and CO_2 , which must be removed as quickly as possible due to the negative feedback effect on fermentation. This is done in the rumen by strictly anaerobic microbes, which utilize the H_2 and CO_2 as substrates and in the process produce a variety of substances (Moss et al., 2000). Two relevant groups are acetogenic bacteria, which produce short-chain hydrocarbons, or methanogenic archaea, which produce CH_4 (Boadi et al., 2004; Garnett & Eckard, 2024). In the rumen, methanogenic archaea are often the dominant group, as they can metabolize H_2 and CO_2 more efficient (Moss et al., 2000). This also means that completely eliminating methanogenic archaea would not be advisable since, according to Morvan et al. (1994), H_2 would accumulate, making digestion in cattle less efficient.

However, the goal of the immunization strategy is to shift the microbiome toward a higher proportion of acetogenic bacteria by training the cattle's immune system to recognize and attack methanogenic archaea (Malyugina et al., 2025). This would result, on the one hand, in less methane production and, on the other hand, in the production of more short-chain hydrocarbons as acetate or butyrate that can still be digested and absorbed by the cattle. In theory, this would also lead to a more efficient digestion (Boadi et al., 2004; Malyugina et al., 2025; Moss et al., 2000). Already, there were some experiments trying to immunize cattle against methanogenic archaea with an inactivated vaccine. But the success was low and inconsistent, mainly due to high surface variability of methanogens (Malyugina et al., 2025; Wright,

2004). To solve this problem a robust and specific antigen has to be found for the dominant methanogen species. The problem here, however, is that while the composition of anaerobic, methanogenic archaea in the rumen is now somewhat better understood (four main groups and the dominant genus is *Methanobrevibacter*, which accounts for approximately 60 %), the individual species remain poorly understood and characterized, even though some of them have already been isolated (Baca-González et al., 2020).

Here, the strains *Methanobrevibacter thaueri* CW^T and *Methanobrevibacter boviskoreani* AbM4 isolated from the rumen of cattle will be further investigated (Lee et al., 2013; Miller & Lin, 2002). For this purpose, the investigation will have two sites. First, investigate growth behavior of the cell under various conditions. Second, trying to implement for the first time a genetic tools for *Methanobrevibacter*. Following the approach of Fink et al. (2021) and Klein et al. (2025) for interdomain conjugation and markerless mutagenesis of *Methanothermobacter*, *Methanobrevibacter* is transformed via conjugation with *Escherichia coli*. Thereby a suicide plasmid was used, with four main functional sites to allow the selection of transformed *Methanobrevibacter* and also the counterselection to enable genome editing (Figure 2).

The first functional site is the "*E. coli* cassette + conjugation-gene". This is important for preparing the donor organism (*E. coli*) for the conjugation to transform the *Methanobrevibacter* species. Therefore the plasmid contains for the transformation of *E. coli* an ORI and a selection marker (*catP*) against chloramphenicol. In addition, the *traJ*-gene is needed for the conjugation. The remaining sites on the plasmid are for the *Methanobrevibacter* species. So the *pac*-gen with its promoter is the selection marker for transformed *Methanobrevibacter* against puromycin (Puro). The "Homology arms" site contains the segments of the genomic DNA (gDNA) from the transforming *Methanob.*. The homology regions thereby flank the gene to be deleted. Through single homologous recombination events, the plasmid is first integrated and then removed again via counterselection, whereby the gene flanked by the homology arms is also excised (Klein et al., 2025). The last of the four sites is hypoxanthine phosphoribosyltransferase (*hpt*) gene, which enhances sensitivity against base-analogue 8-Azahypoxanthin (8-Aza) for the counterselection.

In the following experiments, regions on the homology arms are selected that flank the *hpt* of the respective organism, resulting in a mutant lacking genomic *hpt*. This makes it possible to target any other gene in the genome by selecting the appropriate homology regions and removing them via markerless counterselection (Klein et al., 2025).




Figure 2: Sketch of the general structure of the suicide plasmids for the transformation of *Methanobrevibacter thaueri* CW^T and *Methanobrevibacter boviskoreani* AbM4 via conjugation using *E. coli*. The plasmid contains the ORI for replication in in gram negative bacteria (*E. coli*) and *catP* as a selection marker against chloramphenicol (*E. coli* cassette), as well as the conjugation gene *traJ*. In addition, all plasmids contain the *hpt* gene to enhance sensitivity against the base-analogue 8-Azahypoxanthin, which is used for counterselection, and the two homology arms that flank the genomic *hpt* gene of the corresponding organism. The final important region is the one containing the *pac* gene and its associated promoter, which serves as a selection marker.

1.2 Evaluation based on calculated CH₄ emission

Based on a closer examination of three countries (DEU, NZL, USA), the mitigation strategy “immunization of cattle” will be evaluated. First, it has to be checked if the global methane emission patterns earlier in the introduction fit on the national scale and cattle is a valid target for mitigation. Second, the calculation of methane emission is based on the guideline developed by the intergovernmental panel on climate change (IPCC) in the year 2006 (IPCC, 2006a) and its refinement in 2019 (IPCC, 2019). This guideline standardized the international calculation of national GHG emission for all emission sources.

To calculate methane emissions resulting from enteric fermentation processes in cattle (IPCC, 2006b, 2019), cattle are typically divided into two subcategories: “dairy” and “non-dairy” cattle. Emissions are first calculated separately for these two categories and then summed. There are three different calculation methods (Tier 1 through 3), which differ in their complexity and the amount of data required.

The Tier 1 approach is quite straightforward. The number of animals in the corresponding animal category is multiplied by the appropriate emission factor (EF), which is provided as a default value by the IPCC and specifies how much methane is emitted per animal (IPCC, 2006b, Eq. 10.19). In Tier 2, this EF is now calculated for each animal category and country based on specific local activity data. Here, the gross energy intake (GE) per animal is calculated from energy consumption and the average digestibility of food (DE). The EF is then

obtained by multiplying the GE by the methane conversion factor (Y_m), which can be taken as the default value from the IPCC or has been scientifically determined for the respective country and animal category (IPCC, [2006b](#), Eq. 10.21). Tier 3 involves even more complex calculations and uses detailed, mechanistic models or direct measurements at the farm or animal level (e.g., individual feeding data, respiratory gas measurements of individual animals) (IPCC, [2006a](#)).

The mitigation strategy "immunization of cattle" influences clearly impact two values of the Tier 2 approach. First the Y_m , whereas a shift in the rumen microbiome towards non-methanogenic microbes leads logically to a lower energy conversion into methane. Second the DE, as described in Section [1.1](#), the microbiome shift is expected to lead to increased digestive efficiency, since less energy is converted into methane, which cannot be utilized, and more into short-chain hydrocarbons that can be absorbed by the cattle. The performed calculation of methane emission followed the Tier 2 approach (Section [2.2](#) and Section [3.2.2](#)).

2 DATA AND MATERIALS

2.1 Biochemistry

2.1.1 Organism

Methanobrevibacter thaueri CW^T and *Methanobrevibacter wolinii* SH^T were provided by Dr Graeme Attwood (Bioeconomy Science Institute Ltd (BSI), Palmerston, New Zealand). *Methanobrevibacter boviskoreani* AbM4 and *Methanobrevibacter millerae* SM9 were provided by Lucidome Bio Limited and Dr Graeme Attwood (Bioeconomy Science Institute Ltd (BSI), Palmerston, New Zealand). *Escherichia coli* WM6026 and WM6029 were provided by Prof. William Metcalf (University of Illinois at Urbana-Champaign, IL, USA). *Escherichia coli* DH5 α from Thermo Fisher Scientific Inc. (MA, USA).

2.1.2 Chemicals

All chemicals are from Carl Roth GmbH + Co. KG (Germany) unless explicitly labeled otherwise. Following chemicals were used in the experiments: Brain heart infusion (Merck KGaA, Germany), Proteose peptone, Yeast extract (Oxoid, UK), Na-acetate (Sigma-Aldrich, Merck KGaA, Germany), Na-formate (Sigma-Aldrich, Merck KGaA, Germany), Sodium resazurin, NaHCO₃, KH₂PO₄, MgSO₄ x 7 H₂O, NaCl, NH₄Cl, CaCl₂, HCl, FeCl₂ x 4 H₂O, ZnCl₂, MnCl₂ x 4 H₂O, H₃BO₃, CoCl₂ x 6 H₂O, CuCl₂ x 2 H₂O, NiCl₂ x 6 H₂O, Na₂MoO₄ x 2 H₂O, Vitamin B₁₂, p-Aminobenzoic acid (Aldrich, USA), D-(+)-biotin, Nicotinic acid (Sigma-Aldrich, Merck KGaA, Germany), Calcium pantothenate, Pyridoxine hydrochloride, Thiamine-HCl x 2 H₂O, dithiothreitol, Coenzyme-M (Sigma-Aldrich, Merck KGaA, Germany), FeSO₄ x 7 H₂O, H₂SO₄, Isobutyric acid, DL-2-Methylbutyric acid, Valeric acid, Isovaleric acid, Milli-Q H₂O, Agar-Agar Kobe I, N₂-gas (Air Liquide S.A., France), N₂-CO₂ gas mix (Air Liquide S.A., France), H₂-CO₂ gas mix (Air Liquide S.A., France), LB-Media, glycerol, agarose, TAE-buffer, Gel Loading Dye Purple (6X) (New England Biolabs, USA), GelRed (Biotium, USA), GeneRuler 1 kb DNA Ladder (Thermo Fisher Scientific, USA), ddH₂O, ethanol $\geq 99.5\%$, puromycin (Fisher BioReagents from Thermo Fisher Scientific, USA), chloramphenicol (CAP) (Sigma-Aldrich, Merck KGaA, Germany), cycloserine, 8-Azahypoxanthin (Thermo Fisher Scientific, USA), dimethylsulfoxid, diaminopimelic acid. Restriction enzymes NotI, AscI, SmaI, and FseI, as well as Q5[®] High-Fidelity DNA Polymerase and OneTaq[®] DNA Polymerase, were obtained from New England Biolabs (USA).

All primers used in this study are listed in Table B7, including their target sequence and

corresponding annealing temperature (T_a) for Q5 and OneTaq polymerase. Primers were designed using the NEB[®] Primer Design Tools (New England Biolabs, USA) and synthesized by IDT Biologika (Germany).

2.1.3 Materials

Anaerobic cultivation was performed in serum bottles sealed with butyl rubber stoppers. Syringes (1 mL and 2 mL, Luer-Lock; Chirana T. Injecta, Slovakia) as well as 5 mL and 10 mL syringes (CODAN, Denmark) were used. Cannulas (Sterican[®], B. Braun, Germany; 0.60 x 30 mm) were used for culture handling. Sterile filtration of syringe-applied solutions was performed using Chromafil[®] CA-20/25 S syringe filters (Macherey-Nagel, Germany). Anaerobic jars (Raff + Grund GmbH, Germany) were used for anaerobic incubation. Plasmid DNA was extracted using the Monarch[®] Spin Plasmid Miniprep Kit (New England Biolabs, USA). DNA fragments were purified from agarose gels using the Monarch[®] Spin DNA Gel Extraction Kit (New England Biolabs, USA). Genomic/microbial DNA was extracted using the NucleoSpin[®] Microbial DNA Kit (Macherey-Nagel, Germany).

2.2 Geography

2.2.1 Study area

The geodata analyses of methane reduction potential in rumineszenz will focus on the impact of the mitigation strategy "immunization of cattle". Two emission sectors of agriculture discussed in the IPCC (2019) could be effected of this. On the one hand methane resulting from enteric fermentation and on the other hand from manure management. However, in this bachelor thesis the manure management sector will not be investigated, primarily due to as-yet-unclear links to a possible microbiome shift, as well as time constraints. All calculations are based on the methodology described in IPCC (2019) for calculating CH₄ emission from enteric fermentation in cattle. Furthermore, is the calculation done for only three countries: Germany (DEU), New Zealand (NZL) and United States of America (USA). These three countries were picked, because of three main reasons.

First, the project partners for the biochemical research project to develop an immunization method of cattle against methanogen archaea are located in those very countries.

Second, all three countries belong of the ANNEX-I states. This means that, due to their larger economies and higher levels of consumption, they emit a notable amount of GHGs, including CH₄, and therefore bear a greater responsibility with regard to climate change and

its mitigation. In addition, they also have the financial resources to implement and research the mitigation strategy.

Third, although all three are categorized as ANNEX-I states, there are some clear difference between those countries, as e.g. in their size in terms of area, population, and economy (the US. and Germany as leading economic nations of the world after GDP (International Monetary Fund, [n.d.](#))) or in their predominant way to raise animals, particularly cattle (e.g. in New Zealand (NZL) pasteur grazing is dominant in Germany loose housing (MfE, [2026](#), p. 155; Niebuhr et al., [2026](#), Table 510)).

The time period considered in this bachelor's thesis is determined by the data series published in the CRTs (1990–2024 for DEU and NZL, and 1990–2022 for the USA) as well as by the reference data used to evaluate the "immunization of cattle". For the latter, the decade 2010–2019, as used by Saunois et al. ([2025](#)) for the calculation of an averaged yearly growth of methane, is relevant, along with 2030 as the target year for the emission reduction goals of the GMP.

2.2.2 CRT Data

Common reporting table (CRT) is the data source for the calculations performed. The CRTs were downloaded from the UNFCCC ([2026](#)). For Germany and New Zealand, the published data range from 1990 to 2024, and for the United States, from 1990 to 2022. Where is one CRT published per year and the values represent thereby the average of an entire year. For the analysis of methane emissions from enteric fermentation processes involving cattle, the "Table3" and "Table3.A" sheets of the .xlsx files were used. These show only the values for the year it was published for. The "TableS3" sheet serves as the basis for analyzing methane emissions from the various sectors in each country as well as total emissions, so it summarizes the previous detailed tables of the .xlsx file. This sheet lists not only the values for the current year but also all past years, so the CRT for 2024 and 2022 for the U.S. also includes all values for the remaining years.

Germany and New Zealand have defined two subcategories for cattle according to IPCC ([2019](#)): "dairy cattle" and "non-dairy cattle." The United States, on the other hand, chose to define its own subcategories for cattle, so that "dairy cattle" and "non-dairy cattle" were further subdivided (EPA, [2024](#)). Section Section 3.2.1 explains how the data was processed to ensure that all three countries are comparable with one another. The used variables from the CRT table are given in following units for each animal category:

- CH₄ emission in kt CH₄
- Ym in %
- Population size in 1000s
- DE in %
- GE in MJ head⁻¹ year⁻¹

2.2.3 Reference data

In this bachelor thesis two different scaled data for methane emission are taken into account as a reference to evaluate the possible impact of the mitigation strategy against methane emissions derived from cattle enteric fermentation processes. On the global scale Saunio et al. (2025, fig. 7) calculated the average yearly growth rate of methane 20.9 Tg CH₄ for the decade 2009 – 2010. Here they also used the tier 1 and tier 2 calculation guidelines of the IPCC (2006a). On the national scale the global methane pledge (GMP) was used. The GMP calls for a methane emission reduction of each country until 2030. The aim is hereby to emitted 30 % less methane over all sectors than in 2020 and 40 % less than in 2010. Germany, USA and New Zealand signed this pledge in the year 2021 (Appelhans et al., 2025; CCAC, n.d.). Because of that this serves as a reference on a country scale.

In this thesis the focus is on the strategy of immunization of cattle and not possible others, as e.g. food additives. These are used only selectively to compare what makes immunization unique and how it measures up against them.

2.3 Software

All analyses and processing of the data as well as the visualization took place in R (version 4.6.1). The main package used for processing and analyses was "tidyverse" and "purrr". The visualization was performed via "ggplot". For more information on that, check the R scripts. One exception is some tables were directly written in LaTeX and the plasmid maps were visualized in Google Slides. SnapGene, NCBI, and NEB® Primer Design Tool were used for designing and proofing of DNA primers.

3 METHODS

3.1 Biochemistry

3.1.1 Liquid media preparation for *Methanobrevibacter*

For DSM 1523, chemicals were mixed in MilliQ-H₂O as listed in Table 2, and for DSM 119 following Table 3, except NaHCO₃. The needed trace element solution and solution A for DSM 1523 and 119 were premixed as shown in Table B3 and Table B1. FeSO₄ x 7 H₂O solution (0.1 % w/v) and fatty acid mixture were premixed as listed in Table B6 and Table B5.

Table 2: Composition of the starting solution for the preparation of DSM 1523. The quantities listed are for 1 L. Final concentration of defined chemicals are shown as well. The final pH should be between 6.8 and 7.0. Solutions that have already been premixed are shown in bold. Composition of **solution A** is listed in Table B1 and for **Trace element solution SL-10** in Table B3.

ingredient	quantity	concentration
Solution A	10.00 mL	1 %
Trace element solution SL-10	1.00 mL	0.1 %
Brain heart infusion	6.00 g	–
Proteose peptone	6.00 g	–
Yeast extract	2.00 g	–
Na-acetate	1.00 g	12.19 mM
Na-formate	2.00 g	29.41 mM
Sodium resazurin (0.025 % w/v)	4.00 mL	0.4 %
NaHCO ₃	4.00 g	47.62 mM
Milli-Q H ₂ O	985.00 mL	–

Table 3: Composition of the starting solution for the preparation of DSM 119. Final concentrations for defined chemicals were calculated as well. The quantities listed are for 1 L. The final pH should be between 6.8 and 7.0. Solutions that have already been premixed are shown in bold. Composition of **solution A** is shown in Table B1, of **Trace element solution SL-10** in Table B3, of **FeSO₄ x 7 H₂O solution (0.1 % w/v)** in Table B6, of **Fatty acid mixture** in Table B5.

ingredient	quantity	concentration
Solution A	10.00 mL	1 %
Trace element solution SL-10	1.00 mL	0.1 %
Yeast extract	1.00 g	–
Na-acetate	1.20 g	14.63 mM
Na-formate	2.00 g	29.41 mM
Sludge fluid	50.00 mL	5 %
FeSO₄ x 7 H₂O solution (0.1 % w/v)	2.00 mL	0.2 %
Fatty acid mixture	20.00 mL	2 %
Sodium resazurin (0.025 % w/v)	4.00 mL	0.4 %
NaHCO ₃	4.00 g	47.61 mM
Milli-Q H ₂ O	918.00 mL	–

After boiling, the mixture was sparged with N₂ or N₂/CO₂. Once the solution was cool

enough, NaHCO_3 was added, and the solution was aliquoted into serum bottles, typically 20 mL for routine cultivation. The bottles were also gassed and then sealed with butyl stoppers and aluminum crimp seals. The gas was exchanged to H_2/CO_2 by evacuating four to six times down to -1 bar and refilling with the gas to 1 bar. Autoclaving (121 °C for 20 min) was then performed, after which the solution should no longer show any red discoloration.

Before inoculating with 2 mL of a pre-grown *Methanobrevibacter* culture per 20 mL of medium, 0.2 mL of a sterile DTT solution (30 g/L; 194.55 mM), sterile solution B (mixed as listed in Table B2), and 0.4 mL of a sterile CoM solution (25 g/L) were added. For solution B, the premixed seven-vitamin solution (Table B4) was sterile-filtered and added after CaCl_2 was mixed, aliquoted into a serum bottle, gassed with N_2 or N_2/CO_2 , and autoclaved. In addition, when needed, antibiotics were added. Furthermore, for DSM 119 Wolin's vitamin solution, prepared according to DSMZ specifications, was sterile added instead of the seven-vitamin solution. The cultures were then incubated on a shaker at 37 °C, 120–140 rpm.

3.1.2 Solid media preparation for *Methanobrevibacter*

Spread Plating

The media preparation generally followed the instructions for DSM 1523 (Section 3.1.1). However, here 50 mL were aliquoted into a serum bottle containing 0.75 g agar (1.5 %). Another deviation is that here the headspace was not exchanged to H_2/CO_2 , but instead evacuated and refilled four to six times with N_2 or N_2/CO_2 . Before pouring the plates, they were heated in a water bath and transferred into the glove-box, where 0.5 mL DTT (30 g/L; 194.55 mM) and solution B, as well as 1 mL CoM (25 g/L), were added. 100 µL of a pre-grown culture then were spread plated. The plates were then placed into a jar, which was sealed before being taken out of the glove-box. After changing the atmosphere in the jar to H_2/CO_2 , the plates in the jar were incubated at 37 °C. If the pressure dropped below 0.7 bar, the gas was refilled.

Pour Plating

Here, 50 mL DSM 119 was aliquoted into a serum bottle containing 0.5 g agar (1 %). After transferring the heated DSM 119 (1 % agar) in the glove-box 0.1 mL dithiothreitol (DTT), 0.5 mL solution B and 1 mL CoM was added. After 200 µL of a pre-grown culture were put in the empty petri dish, the still liquid DSM 119 were poured onto it. Following that, the petri dishes were moved in an eight shaped form to distribute the organism. Plates were then transferred outside of the glove-box in a gas tight jar. Before incubated by 37 °C, the gas was wxchanged to H_2/CO_2 . If the pressure dropped below 0.7 bar, the gas was refilled.

Roll plating

10 mL of DSM 1523 is prepared in a serum vial that is usually used for 20 mL of medium, following the procedure described above. Here, the vial contains 0.15 g agar before the prepared medium is aliquoted. Before autoclaving, the gas is exchanged to H₂/CO₂ by evacuating four to six times to -1 bar. For Plating, the serum bottle is heated in a water bath until the agar is liquid, then, after brief cooling, 0.2 mL DTT and solution B, as well as 0.4 mL CoM, are added. The concentration of these three ingredients is thus double the usual amount. Either 200 µl or 400 µl of a pre-grown culture were added, at which point the medium should still be completely liquid and at a temperature of approximately 50 °C. Once inoculated, the still completely liquid culture is spun in a horizontal position on an ice bath. It is important that the bottle is rotated as fast as possible in the same horizontal position in the ice bath, so that a clean, thin layer forms around the inside of the serum bottle. Otherwise, the agar becomes chunky, which considerably hinders the identification of growing colonies. Afterwards, the cultures are incubated in a vertical position at 37 °C, and the gas has to be replenished regularly (every 2 to 4 days).

3.1.3 Cell counting

Cell counting was performed with a phase-contrast microscope (Carl Zeiss, Germany) at 400 x magnification and a Neubauer improved counting chamber, except the *M. wolinii* sample with an optical density at 600 nm (OD₆₀₀) of 0.387 was counted using a Bürker counting chamber. In the Bürker chamber, the squares were counted, whereas in the Neubauer improved chamber, the group squares were counted. Both have a volume of $4 \cdot 10^{-6}$ mL, as can be seen in LO - Laboroptik GmbH ([2026](#)). It is important to note that counting was not restricted to a single focal plane. Instead, all planes were scanned through and the cells counted accordingly. In addition, the top and left edges of the squares were included in the count, but the bottom and right edges were not. Before cell counting, the OD₆₀₀ was measured with a 20 GenesysTM photometer (Spectronic Instruments, USA). Samples were diluted 10- or 20-fold in DSM 1523. Four chambers were filled for counting, and for each chamber, four squares were counted, except for *M. millerae*, where five squares were counted for three chamber fillings, and only two squares for the remaining chamber filling.

3.1.4 Sensitivity experiments

Puromycin was tested at five different concentrations (1, 2, 5, 10, and 20 µg/mL) in triplicates using 20 mL DSM 1523 to assess its effect on *Methanobrevibacter boviskoreani* AbM4 and *M. thaueri* growth. For the three lowest concentrations, a sterile stock solution of 228 µg/mL puromycin in MilliQ-H₂O was prepared; for the two highest concentrations, a stock solution of 2280 µg/mL was used. A control without any additives was included. Cultures were incubated at 37 °C and 120–140 rpm. The OD600 was measured once a day, using DSM 1523 medium as blank, and dilutions, if necessary, were also performed with DSM 1523.

The effect of 8-Azahypoxanthin on *M. boviskoreani*, *M. thaueri*, and *M. millerae* was tested at five different concentrations (100, 250, 500, 750, and 1000 µg/mL, including a positive control without any additives and a solvent control with 1 mL of DMSO. The experiment was performed in triplicates in 20 mL DSM 1523. A 22.8 µg/mL 8-Azahypoxanthin stock solution in DMSO was prepared. Cultures were incubated at 37 °C and 120–140 rpm. The OD600 was measured once a day, using DSM 1523 medium as blank, and dilutions, if necessary, were also performed with DSM 1523. In addition, an uninoculated control was prepared for the 8-Aza sensitivity assay of *M. thaueri* to assess the influence of DMSO on the medium. For this, 20 mL DSM 1523 was supplemented with 1 mL DMSO. This preparation was incubated under the same conditions (37 °C, 120–140 rpm), and the OD600 was measured once a day.

3.1.5 Plasmid construction

In-silico design for suicide plasmids used for *hpt*-gene knockouts in *M. thaueri* and *M. boviskoreani* was performed with SnapGene (Dotmatics, USA) according to the scheme shown in Figure 2. All created plasmids are listed in Table B15. For the plasmids, the original *pac* sequence from *Streptomyces alboniger* was codon-optimized for the respective archaea (*pac_opt*). All primers used in this study are listed in Table B7. All restriction digestions were performed following the Optimizing Restriction Endonuclease Reaction protocol from NEB (USA). PCR (Mastercycler nexus gradient with flexlid, Eppendorf, Germany) of inserts was performed with Q5[®] High-Fidelity DNA Polymerase following the instructions from NEB. Digested vector and PCR DNA fragments were purified on a 1.5 % agarose gel (100 V, 35 min) and extracted using the Monarch Spin DNA Gel Extraction Kit following the manufacturer's instructions, excluding the elution step. Here, a dry centrifugation step (Mikro 22 centrifuge, Andreas Hettich GmbH & Co. KG, Germany) was added before elution was performed with autoclaved ddH₂O. In addition, a Biometra TS1 Thermoshaker (Analytik Jena, Germany) was used for heating. All plasmids were assembled via Gibson assembly following the NEB[®] HiFi

DNA Assembly Reaction protocol. Assembled plasmids were used to transform chemically competent *E. coli* DH5 α cells and were harvested using the Monarch Spin Plasmid Miniprep Kit, following the kit instructions with two modifications. First, for the lysis step, after addition of lysis solution B2, the mixture was inverted 4 to 5 times, and the neutralization solution was then added directly. The mixture was then inverted until the solution turned completely yellow. Second, elution was not performed with the prescribed elution buffer but with autoclaved ddH₂O, and a dry centrifugation step was performed once before elution. All plasmids were verified via Nanopore sequencing (Eurofins Genomics GmbH, Luxembourg).




Figure 3: Suicide plasmid maps for transformation by conjugation for *M. thaueri* and *M. boviskoreani*. pMt_0321_hpt (6254 bp) is the parent plasmid used to construct the other two, pMt_0231_hpt (6145 bp) and pMb_0231_hpt (6214 bp). The maps show only the gene regions (between the dashed lines) that have been modified, as well as the restriction site sites (at the end of the dashed lines) used or the newly created restriction site sites. The new produced plasmids were verified via nanopore sequencing.

Two of these plasmids (Table B15) were created: pMt_0231_hpt and pMb_0231_hpt. First, the initial plasmid pMr_0321_hpt (Flaiz, unpublished) was digested with NotI and AscI to remove the homology arm region. Simultaneously, the left and right homology arms for *M. thaueri* were amplified using primer pairs 48/49 and 50/51, respectively, with genomic DNA (gDNA) from *M. thaueri* as template. The gDNA was extracted from a grown culture using the NucleoSpin Microbial DNA Kit, following the manufacturer's instructions except that autoclaved ddH₂O was used for elution instead of the kit elution buffer, with an additional dry centrifugation step before elution. After purifying the DNA fragments and measuring their concentration with the EzDrop 1000 (Blue-Ray Biotech, Taiwan), the pMr_0321_hpt backbone and the amplified homology arms were assembled into pMt_0321_hpt.

pMt_0321_hpt served as the precursor for the target plasmids (Figure 3) and was digested with FseI and SmaI to remove the *pac* gene together with its promoter. For the assembly, an insert containing the codon-optimized *pac* gene for the corresponding *Methanobrevibacter* and the *PhmtB* promoter, with an additional SpeI restriction site between promoter and gene, was designed in-silico with SnapGene and synthesized by IDT. This insert was amplified with primer set 17/63 for *M. thaueri* and 17/71 for *M. boviskoreani*. Gibson assembly yielded two plasmids: the correct pMt_0231_hpt and pMt_0231_hpt containing the codon-optimized *pac* gene for *M. boviskoreani*. The latter was subsequently digested with NotI and AscI, and the *M. boviskoreani* homology arms were amplified with primer sets 52/53 (left arm) and 54/55 (right arm), using extracted *M. boviskoreani* gDNA as template. After purification, the backbone and homology arm regions were assembled to pMb_0231_hpt and cloned into *E. coli* DH5 α .

3.1.6 Transformation of *Methanobrevibacter*

All 28 preparation lines are listed in Table B16. Figure 4 visualizes the general approach taken in this bachelor thesis to transform three *Methanobrevibacter* species: *M. thaueri*, *M. boviskoreani*, and *M. millerae*. Thereby, DAP-auxotrophic *E. coli* WM6026 and *E. coli* WM6029 were transformed with plasmids (pMt_0231_hpt, pMm_0231_hpt, pMb_0231_hpt) on selective agar plates containing 0.1 mM DAP and 30 μ g/mL CAP.

The day before the mating (Day 0, Figure 4), 5 mL LB medium containing 0.1 mM DAP and 30 μ g/mL CAP was inoculated with each possible combination of *E. coli* WM6026 and *E. coli* WM6029 and the named plasmids, and incubated overnight at 37 °C and 120–140 rpm.

On the day of the mating (Day 1), 20 mL LB medium with 0.1 mM DAP and 30 μ g/mL CAP was inoculated with 1 mL of the overnight *E. coli* culture and cultivated (37 °C, 120–140 rpm) for 4.5 h, except for the preparation with *M. boviskoreani** (Table B16), where 1.5 mL was used for inoculation and the *E. coli* cultures were cultivated for 3.75 h. Final OD600 was measured before the 20 mL *E. coli* cultures were divided into 10 mL aliquots and centrifuged twice (Centrifuge 5910R, Eppendorf, Germany); the supernatant was decanted, and the pellets were washed once with 1 mL of DSM 1523. Centrifugation was performed for 5 min each time, at 6000 rcf the first time and 9000 rcf the second time. In addition, 50 mL DSM 1523 (1.5 % agar) was prepared with 10 mM MgSO₄, 5 mM CaCl₂, and 0.1 mM DAP. *E. coli* pellet, the prepared liquid agar medium, as well as a full-grown *Methanobrevibacter* culture were transferred inside the glove-box. Colonies that had grown on that same day were marked with an asterisk.




Figure 4: Methodological approach to transform a *Methanobrevibacter* (*Methanob.*) species via interdomain conjugation using two diaminopimelic acid (DAP) auxotrophic *E. coli* strains, WM6026 and WM6029. Suicide plasmids corresponding to the targeted *Methanob.* species were used, containing chloramphenicol (CAP) as a selection marker for *E. coli* and puromycin as a selection marker for the transformed *Methanob.* Two recovery periods were tested: Recovery A (approx. 5 h) and Recovery B (approx. 20 h).

Inside the glove box, *Methanobrevibacter* culture was transferred into 50 µl falcon tubes, centrifuged (10 min, 8000 rcf) outside the glove box, and transferred back into the glove box. The *Methanobrevibacter* pellet was resuspended in 600 µl DSM 1523. Aliquots of 300 µl of this resuspended culture were used to separately resuspend the *E. coli* WM6026 and WM6029 pellets carrying the corresponding plasmid. These 300 µl mixtures of *Methanobrevibacter* and *E. coli* were spot-plated (4 to 5 spots per plate) on the previously described DSM 1523 (1.5 % agar). The plates were transferred in an airtight anaerobic jar out of the glove box, the gas was changed to H₂/CO₂, and the jar was incubated overnight at 37 °C.

On the following day (Day 2), the incubated plates and two bottles per plate containing 10 mL DSM 1523 medium supplemented with 200 µg/mL cycloserin were transferred into the glove-box. The spots were gently scraped off the plate with a spatula together with 2 mL of medium, and 1 mL of this suspension was then transferred back into each of the 10 mL bottles. The bottles were transferred back outside and incubated at 37 °C and 120–140 rpm for different recovery time periods (t_P) before adding 20 µg/mL puromycin. The 10 mL bottle per plate with the shorter recovery time was marked A (approximately 5 h), and the other B (approximately 20 h). Figure 4 visualizes the approach up to this point.

All cultures were subsequently subcultured two more times into fresh selective DSM 1523 medium containing 200 µg/mL cycloserin and 20 µg/mL puromycin. The time between these two transfers (t_{2_1}) as well as the time from the end of recovery to the first transfer (t_{1_1}) were recorded. The gDNA of growing cultures was extracted using the NucleoSpin® Microbial DNA Kit following the manufacturer's instructions, except for the elution step, where autoclaved ddH₂O was used instead of the kit's elution buffer, and a dry centrifugation step was added before elution. For cell lysis, a bead beater (MP Biomedicals) was used. Using the gDNA as template, the 16S rDNA of archaea was amplified with primer set 22/23 (Table B7), and the bacterial 16S rDNA with primer set 1/2; a PCR with OneTaq® DNA Polymerase was performed following the instructions from NEB (USA). 16S-Sequencing was performed via Sanger sequencing (Eurofins Genomics GmbH, Luxembourg). In addition, a Q5 polymerase PCR was performed with primer set 38/39 to amplify an 838 bp fragment of the suicide plasmids used. Primer set 38/39 was checked for off-target products smaller than 4000 bp in *M. boviskoreani*, *M. millerae*, *E. coli*, and *Staphylococcus epidermidis* via NCBI Primer-BLAST (USA), using default settings for primer specificity stringency and the RefSeq reference genomes as the database.

A gel (1.5 %) image was taken of this 838 bp PCR product and of two independently performed 16S rDNA amplifications using different, older primer preparations, which had pre-

viously been verified using a negative control. GelRed, Gel Loading Dye Purple (6X), and 1 kb GeneRuler were used as the ladder for the 1.5 % agarose gel.

3.1.7 Ethanol as alternative substrate

5 concentration of EtOH (10, 20, 50, 100 and 200 mM) were tested in media, where the headspace was sterile changed to N₂/CO₂ before inoculation with *M. boviskoreani*, *M. thaueri* or *M. wolinii*. For *M. boviskoreani* and *M. wolinii* DSM 1523 was used, for *M. thaueri* DSM 119. Incubation was done at 37 °C and 120–140 rpm.

3.2 Geography

The general procedure for the processing, analyses and visualization of the CRT data in R is described in the part below. For a more detailed overview, please check the R scripts.

3.2.1 Processing CRT-Data

Cattle enteric fermentation

For Germany and New Zealand all given data for cattle and its subcategories "dairy cattle" and "non-dairy cattle" were imported from the "Table3.A" sheet of the CRT tables for each year, and processed so, that for each year of each country a table was created with one column with the year, one column with the cattle type and the following columns are for the measured or calculated values. Afterwards, all one year tables of one country were merged, so that one country has one table, where the values for the cattle categories from 1990 to the last published year are present.

For the U.S. there are no direct "Dairy cattle" and "Non-dairy cattle" categories, but more detailed one. So after the import of the same value columns for each cattle category as described before, these more detailed subcategories have to be merged in the same 2 as for Germany and New Zealand. For this purpose, the official definition and classifications from the U.S. (EPA, [2024](#), Chapter 5, p. 6) were used. DE, GE and Ym were merged as a weighted mean with the populations as weight. The methane emission were summed.

Methane emission for each sector

For sector-specific emissions, only the "TableS3" sheet was used for the most recent CRT (for the U.S., the year 2022; for Germany and New Zealand, the year 2024). Here, all sectors and their subcategories were imported for all years, as were the total emissions. After processing

the data, only the methane emission values for the sectors in general were retained, as well as the total methane emissions for each country.

3.2.2 Calculation of methane emissions from enteric fermentation processes in cattle

The total methane emission for cattle and its subcategories dairy and non-dairy was calculated following the Tier 2 approach from IPCC (2006a) via the indicators Y_m , GE and the population number of the animal categories. Therefore, the CH_4 emissions were calculated for dairy and non-dairy cattle following the eq. (1). The methane emission for cattle than is the sum of dairy and non-dairy.

$$CH_{4,T} = \frac{GE \cdot \left(\frac{Y_m}{100}\right) \cdot 365}{55.65} \cdot \frac{N_T}{10^6} \quad (1)$$

where:

- $CH_{4,T}$ = yearly methane emission of a animal category [kt CH_4 year⁻¹]
- GE = gross energy intake [MJ head⁻¹ day⁻¹]
- Y_m = methane conversion factor [%]
- 55.65 = energy content of CH_4 [MJ kg⁻¹]
- N_T = population-size of animal category
- 10^6 = conversion-factor kg to kt

3.2.3 Share of cattle methane emissions from enteric fermentation

The share of enteric fermentation was calculated for its fraction on the total amount of anthropogen produced CH_4 in a country and on the methane emissions resulting from the agriculture sector. For this purpose the published data in the CRT was used for each country.

3.2.4 Calculation of saved methane

To calculate the potential methane savings resulting from the mitigation strategy under investigation (immunization of cattle), various success scenarios are defined: 10, 20, 30, 40, and 50 % shifts in the rumen microbiome of cattle from methanogens toward non-methane-producing microbes. These will have an impact on two indicators used in IPCC (2019). Y_m , which represents the proportion of energy or feed consumed by cattle that is converted into

methane by that microbiome, and DE, assuming that the reduced amount of feed energy converted into methane now benefits the animal during digestion, meaning that the percentage of feed digestibility for the animal increases. The values of the resulting Ym (Ym_{Red}) and DE (DE_{Red}) are calculated as in eq. (2) and eq. (3).

$$Ym_{Red} = Ym \cdot \left(1 - \frac{Red}{100}\right) \quad (2)$$

where:

- Ym_{Red} = adjusted Ym for the investigated reduction scenario [%]
- Ym = original methane conversion factor from CRT [%]
- Red = investigated reduction scenario [%]

$$DE_{Red} = DE + \left(Ym \cdot \frac{Red}{100}\right) \quad (3)$$

where:

- DE_{Red} = adjusted DE for the investigated reduction scenario [%]
- DE = Digestibility of feed as a fraction of gross energy intake [%]
- Red = investigated reduction scenario [%]

The eq. (1) presents the linear relation of Ym and methane emission of cattle already. DE, on the other hand, is named in three different equations in the calculation of IPCC (2019), shown here with little adjustments in eq. (4) through (6). It has his impact on produced methane through his role as value for the calculation of GE, which has a linear relation towards methane emission (see eq. (1)).

$$GE = \frac{\left(\frac{NE_x}{REM}\right) + \left(\frac{NE_y}{REG}\right)}{\left(\frac{DE}{100}\right)} \quad (4)$$

where:

- GE = gross energy intake [$MJ \text{ head}^{-1} \text{ day}^{-1}$]
- NE_x = sum of the net energy required for maintenance, activity, lactation, work and pregnancy of the animal [$MJ \text{ head}^{-1} \text{ day}^{-1}$]
- REM = ratio of net energy available in a diet for maintenance (Equation (5))

- NE_y = sum of the net energy required for growth and for wool production [MJ head⁻¹ day⁻¹]
- REG = ratio of net energy available for growth in a diet (Equation (6))
- DE = Digestibility of feed as a fraction of gross energy intake [%]

$$REM = \left[1.123 - (4.092 \cdot 10^{-3} \cdot DE) + (1.126 \cdot 10^{-5} \cdot DE^2) - \left(\frac{25.4}{DE} \right) \right] \quad (5)$$

where:

- REM = ratio of net energy available in a diet for maintenance
- DE = Digestibility of feed as a fraction of gross energy intake [%]

$$REG = \left[1.164 - (5.16 \cdot 10^{-3} \cdot DE) + (1.308 \cdot 10^{-5} \cdot DE^2) - \left(\frac{37.4}{DE} \right) \right] \quad (6)$$

where:

- REG = ratio of net energy available for growth in a diet
- DE = Digestibility of feed as a fraction of gross energy intake [%]

To calculate the new methane emission for cattle corresponding to the reduction scenario, GE has to be recalculated with the adjusted DE. Afterwards eq. (1) can be used again to calculate the adjusted CH₄ emission with the adjusted GE (GE_{Red}) and Ym_{Red}. For calculation the GE_{Red}, DE_{Red} can not just simply be put in the eq. (4), because of the missing values for NE_x and NE_y. Although the values for the individual net energy intake categories (see eq. (4)) should not change, these are not given in the published CRTs of the countries. To solve this problem, two things are assumed:

1. The net energy required for wool production is an irrelevant category for the investigation of cattle.
2. Most of the animal in the population of dairy and non-dairy cattle are fully grown or close to it. Because of that the net energy needed for growth will overlooked and set to 0.

So, eq. (4) can be slimmed down and rearranged to calculate a fix value for NE_x for the corresponding year, because the part with NE_y turns zero (see eq. (7)). For this purpose, GE_{Red} is calculated for a given year using DE_{Red} and the fixed values for NE_x, all due to the assumption that NE_y is 0 (eq. (8)). The calculated gross energy intake is then substituted into

eq. (1) along with the corresponding Ym_{Red} value. This yields the methane emissions ($CH_{4,R}$) for a cattle category under a reduction scenario for a specific year.

$$NE_x = GE \cdot REM \cdot \left(\frac{DE}{100} \right) \quad (7)$$

$$GE = \frac{\left(\frac{NE_x}{REM} \right)}{\left(\frac{DE}{100} \right)} \quad (8)$$

where:

- NE_x = sum of the net energy required for maintenance, activity, lactation, work and pregnancy of the animal [$MJ \text{ head}^{-1} \text{ day}^{-1}$]
- GE = gross energy intake [$MJ \text{ head}^{-1} \text{ day}^{-1}$] (eq. (4))
- REM = ratio of net energy available in a diet for maintenance (Equation (5))
- DE = Digestibility of feed as a fraction of gross energy intake [%]

The saved methane emissions ($CH_{4,S}$) for a specific reduction scenario are calculated by subtracting the original value for methane emissions from the value adjusted for the scenario (eq. (9))

$$CH_{4,S} = CH_{4,T} - CH_{4,R} \quad (9)$$

where:

- $CH_{4,S}$ = saved CH_4 through reduction scenario [$kt \text{ CH}_4 \text{ year}^{-1}$]
- $CH_{4,T}$ = yearly methane emission of a animal category [$kt \text{ CH}_4 \text{ year}^{-1}$]
- $CH_{4,R}$ = yearly methane emission of a animal category for a corresponding reduction scenario [$kt \text{ CH}_4 \text{ year}^{-1}$]

3.2.5 Prediction of CH_4 emission until 2030

Two steps are required to calculate total methane emissions, as well as methane emissions for three reduction scenarios (10, 30, and 50) through the year 2030. First, total methane emissions without emissions from EnterFe processes in cattle are calculated and then extrapolated.

Second, to calculate the methane emission from enteric fermentation (EnterFe) in cattle, the values for DE, Ym, Population size and NE_x were predicted for each subcategorie ("dairy"

and "non-dairy cattle") until 2030. For that, NE_x had to be first calculated (eq. (7)). From the predicted values for these indicators the cattle EnterFe CH_4 emission could be calculated (via eq. (8) and (1)). Also the methane emission values for three different reduction scenarios (10, 30 and 50) were calculated with these values using the eq. (2), (3), (8) and (1). Afterwards, the emissions of the subcategories were summed to the CH_4 emission for cattle resulting from enteric fermentation processes.

Third, the predicted emission values for total without cattle enteric fermentation were added with the calculated emission values for cattle enteric fermentation to achieve the total methane emission of a country.

The forecast until was made using a linear regression for each relevant value. However, the regression was not based on the entire time period, but rather on three different time intervals (the last 5, 10, and 15 years). For each linear model, both the confidence interval (CI) with a confidence level of 95 % and the total emissions were calculated. In addition, the R^2 value was determined for each model. The extrapolation extends from 2025 to 2030 for New Zealand and Germany, and from 2023 to 2030 for USA. All models with their corresponding equation and R^2 for each country are listed in Table B18 through Table B20.

4 RESULTS

4.1 Biochemistry

All following experiments were done with *Methanobrevibacter boviskoreani* AbM4 and *Methanobrevibacter thaueri* CW^T, in some *Methanobrevibacter wolinii* SH^T and *Methanobrevibacter millerae* SM9 were investigated as well.

4.1.1 Cultivation

M. thaueri, *M. boviskoreani* and *M. millerae* were cultivated in DSM 119 and DSM 1523. For DSM 119 no growth curve was measured, but no visual difference was detected. For DSM 1523 growth-curve for *M. thaueri*, *M. boviskoreani* and *M. millerae* were taken as positive control in Figure 8 and 10 for *M. thaueri*, Figure 7 and 9 for *M. boviskoreani* as well as Figure 11 for *M. millerae*. In general, it can be said, based on these growth-curves, that the used *Methanobrevibacter* reach their growth maximum within 2 to 4 days. This maximum is usually around a optical density at 600 nm (OD600) of 0.3 and does not exceed 0.4. Afterwards continuous, usually slightly decline begins, so after 6 to 10 10 days the cultures have an OD600 below 0.1 (Figure 7, 9 and Figure 11). Further growth parameter such as generation time or growth rate were not calculated due to low time resolution (max. one measurement per day).

Nevertheless, some specific growth behavior for *Methanobrevibacter* species could be detected. So *M. millerae* and *M. boviskoreani* grew quite reliably in the described manner, but latter formed precipitates, which were not completely dissolvable through shaking (Figure A1). This was seen in DSM 1523 and DSM 119. *M. thaueri* on the other hand differs a bit in growth from the described manner. So it does not grow as dense with an max. measured OD600 around 0.2 and clearly below 0.3 (Figure 8 and 10). Furthermore, *M. thaueri* lyses notably faster than the other species, so within 3 days the OD600 is for the positive control in Figure 8 below 0.1 and within 5 to 6 days after maximal growth below 0.3. The growth curve of the other species positive control (Figure 7, 9 and 11) dropped not below 0.3 for the investigated time period of up to 14 days. This lysing behavior of *M. thaueri* was also visible in DSM 119 but not so fast. In addition, *M. thaueri* grows much more unreliably, so in Figure 8 within 3 days the max. OD600 was reached while for the positive control in Figure 10, where single triplicates started to grow after 5 to 14 days.

M. boviskoreani and *M. thaueri* showed no visual growth with ethanol (EtOH) as alternative substrate to H₂. EtOH concentration ranging from 10 mM to 200 mM were tested.

4.1.2 Cell count

Cells were counted for *M. boviskoreani*, *M. millerae*, *M. wolinii* and *M. thaueri* with a phase-contrast microscope at 400 times magnification (Table B8 to Table B13). Thereby, the archaea appear as little black dots, who tend to link together in a row or cluster (Figure A2). The cell-number per mL for the cultures then were determined using the following calculation:

$$\text{cellnumber} \cdot \text{mL}^{-1} = \frac{\varnothing \text{ cellnumber} \cdot \text{dilution factor}}{\text{Volume of the counted Square}} \quad (10)$$

To calculate the cell count per mL, the arithmetic mean was determined for each culture (tab. B14) and substituted into the equation 10 along with the corresponding dilution factor (Table B14). The results of the calculation were recorded in table 4. The calculation was performed as an example using *M. wolinii* (OD600 = 0.387):

$$\text{cellnumber} \cdot \text{mL}^{-1} = \frac{216.375 \text{ cells} \cdot 20}{4 \cdot 10^{-6} \text{ mL}} = 1,081,875,000 = 10.819 \cdot 10^8$$

Table 4: Cellnumber per mL of different *Methanobrevibacter* (*Methanob.*) culture for corresponding optical density at 600 nm (OD600). For counting the cells a phase-contrast microscope was used and a Bürker or Neubauer improved counting chamber at a 400 times magnification. The cell count per mL was calculated using the equation 10, and the values were taken from the table B14.

culture	OD600	cellnumber · mL ⁻¹
<i>M. wolinii</i>	0.387	10.819 · 10 ⁸
<i>M. wolinii</i>	0.396	10.672 · 10 ⁸
<i>M. thaueri</i>	0.235	5.603 · 10 ⁸
<i>M. thaueri</i>	0.116	3.644 · 10 ⁸
<i>M. millerae</i>	0.378	8.880 · 10 ⁸
<i>M. boviskoreani</i>	0.287	9.272 · 10 ⁸

In general, calculated cellnumber per mL in Table 4 for the *Methanobrevibacter* species studied ranging from 3.644 · 10⁸ cells/mL for *M. thaueri* (OD600 of 0.116) to 10.819 · 10⁸ cells/mL for *M. wolinii* (OD600 of 0.387). A clear trend, that higher OD600 always correlate with a higher cellnumber/mL is not shown, for example, *M. boviskoreani* (OD600 = 0.287) has a higher cell count per mL (9.272 · 10⁸) than *M. millerae* (OD600 = 0.378 and celnumber per mL = 8.880 · 10⁸) despite having a lower OD600 of nearly 0.1. Furthermore, both *M. wolinii* cultures and *M. millerae* have a nearly similar OD600 values between 0.378 and 0.396 or 0.387, but those of *M. wolinii* are around 2 · 10⁸ cells per mL higher (10.819 or 10.672 · 10⁸ to 8.880 · 10⁸ cells per mL). The *M. wolinii* cultures are quite similar to each other in terms of cell count per mL and OD600, with the higher value cellnumber/mL being calculated for the culture with the lower OD600.

Besides *M. wolinii*, two cultures of *M. thaueri* were also examined to determine cell count. Here, one culture has an OD600 of 0.235 that is slightly more than twice as high as the other one with 0.116, but a cell count per mL that is slightly less than twice as high ($5.603 \cdot 10^8$ to $3.644 \cdot 10^8$ cells per mL).

4.1.3 Plating

Spread plating

M. boviskoreani and *M. thaueri* were cultivated on solid medium (DSM 1523 with 1.5 % agar) as duplicates by spread plating 100 μ l of a full-grown pre-culture. Results of the duplicates are shown in Figure 5.




Figure 5: Spread plating results of *M. thaueri* and *M. boviskoreani*. 100 μ l of a full-grown culture was plated on DSM 1523 (1.5 % agar) in duplicates. Red rectangles highlight gas bubble spots, green rectangles grown colonies. In image A and B *M. boviskoreani* was plated and in image C and D *M. thaueri*. For plate A 47 colonies were counted and for plate B 56, on plate C and D 0 colonies were counted.

Various spots have been identified on all 4 plates. Most of these are gas bubbles, as indicated by the smaller size and transparency of the spots (see red rectangles in Figure

5). In contrast, a few spots are opaque, larger, round, slightly milky, and yellow (see green squares *ibid.*). These are grown colonies. Cultivation of *M. thaueri* with spread plating was not successful (image C and D in Figure 5). *M. boviskoreani*, on the other hand, grew on both plates with 47 counted colonies for one duplicate and 56 for the other. Single colonies were picked from the plates, propagated in liquid DSM 1523, and verified as *M. boviskoreani* via 16S-Sequencing.

Pour plating

The pour plating was not successful for 200 μ l of a full-grown *M. thaueri* culture with DSM 119 (1 % agar) as you can see in fig. A3. This experiment was also performed as duplicate.

Roll Plating

M. thaueri, *M. wolinii* and *M. boviskoreani* have been roll plated in DSM 1523 (1.5 % agar) with once 200 μ l and once 400 μ l inoculation of a full-grown pre-culture. The headspace was regularly charged up for the 200 μ l preparations over a month, for the 400 μ l not. For the 400 μ l there were no visible colonies for *M. thaueri* and just a lot of very, very little potential colonies for *M. boviskoreani* and *M. wolinii*. The 200 μ l, on the other hand, resulted in colonies for all three microbes (Figure 6).




Figure 6: Roll plating of *M. thaueri*, *M. wolinii* and *M. boviskoreani* in 10 mL DSM 1523 (1.5 % agar). 200 μ l of a full-grown culture were used. Differences in the agar structure are due to methodological variations. The green rectangle marks the same colony in C and D. A: *M. boviskoreani*, B: *M. wolinii*, C: *M. thaueri*, D: *M. thaueri* zoomed in on colony.

Although in all three bottles colony forming unit (CFU) were formed (Figure 6) for *M. thaueri* were notable less colonies counted as for the other species. So for *M. thaueri* 15 colonies

were counted while for *M. wolinii* 2432 and for *M. millerae* 3536 were detected, but the colonies of *M. thaueri* were larger (Figure 6). During cultivation the partial pressure dropped. So approximately every two to four days the gas pressure in the bottle dropped from about 1.1 bar to below 0.8 bar and had to be refilled. Verification via 16S-Sequencing, as is done with spread plating, is still pending.

Even though the OD600 of the cultures used was not measured prior to plating, the plating efficiency was estimated. This was done on the assumption that the cultures that appeared visually full-grown had an OD600 approximately equal to those listed in Table 4, with the higher value for cell count per mL always being used.

$$\text{Plating efficiency [ppm]} = \frac{\text{counted CFU}}{\text{number of used cells}} \cdot 10^6 \quad (11)$$

The calculation was based on equation 11 and was performed as follows, for example:

$$\text{Plating efficiency} = \frac{2432}{0.2 \text{ mL} \cdot 10.819 \cdot 10^8 \text{ cells} \cdot \text{mL}^{-1}} \cdot 10^6 = 11.24 \text{ ppm}$$

Table 5: Counted colony forming unit (CFU) and estimated plating efficiency of different *Methanobrevibacter* (*Methanob.*) cultures for the roll plating technique. 200 µL of a full-grown culture was used for plating. For *M. wolinii* and *M. boviskoreani*, only a sixteenth of the bottle was counted. The higher of the two cell number values per mL from table 4 was always used as the reference for the cell count in the initial solution. Plating efficiency was then calculated following eq. (11).

culture	counted CFU	plating efficiency [ppm]
<i>M. wolinii</i>	2432	11.24
<i>M. thaueri</i>	15	0.13
<i>M. boviskoreani</i>	3536	19.07

Table 5 lists the CFU counts per bottle as well as the corresponding plating efficiency. For *M. wolinii* and *M. boviskoreani*, the efficiency is in the lower two-digit ppm range with 11.24 ppm and 19.07 ppm. The efficiency for *M. thaueri* is notable lower, at 0.13 ppm.

4.1.4 Antibiotic sensitivity

Puromycin

Growth experiment for *M. thaueri* and *M. boviskoreani* was performed in DSM 1523 media with various concentration of puromycin (Puro): 0 µg/mL, 1 µg/mL, 2 µg/mL, 5 µg/mL, 10 µg/mL and 20 µg/mL. The experiment was performed in triplicates, with each antibiotic (AB) concentration series inoculated with one full-grown pre-culture. For plotting negative measured OD600 values were set to 0.001. Figure 7 shows the results for *M. boviskoreani* and Figure 8 for *M. thaueri*.




Figure 7: Growth curve in DSM 1523 for *M. boviskoreani* for various concentration of puromycin (Puro): 0 µg/mL, 1 µg/mL, 2 µg/mL, 5 µg/mL, 10 µg/mL and 20 µg/mL. Experiment was performed in triplicates (Cltr. 1, 2 and 3), with each triplicate concentration series is inoculated with its own full-grown pre-culture. The optical density at 600 nm (OD600) of the pre-culture were 0.110 for Cltr 1, 0.091 for Cltr 2 and 0.034 for Cltr 3. The OD600 was plotted on a logarithmic scale against time. OD600 values less than 0.000 were set to 0.001. A non-inoculated DSM 1523 medium solution was used as a blank.

Fig. 7 shows that *M. boviskoreani* exhibits a very similar growth pattern for Puro concentrations of 0, 1, and 2 µg/mL. Exponential growth occurs within the first two days. This is followed by a delayed growth phase, such that the growth maximum is reached between days two and four at an OD600 of around 0.3. Until the final measurement day (day 10), the OD decreases continuously to an OD600 value of around 0.1. One difference that can still be noted here, however, is that the variation between the triplicates at 0 µg/mL is smaller than that observed with Puro. In the latter case, Cltr 3 does not begin exponential growth until one day later as the other triplicates.

When *M. boviskoreani* was cultivated in the presence of 5 µg/mL Puro growth is inhibited as the maximal OD600 is reached only after 8 days. Nevertheless, the maximum OD600 values differ between the triplicates with 0.224 for Cltr 1, 0.130 for Cltr 2 and 0.168 for Cltr 3. are also slightly lower than in the previous growth curves. In addition, the triplicates did not show comparable growth curves: Cltr 3 only started growing after 4 days, whereas the other two started growing immediately but rather slowly, and Cltr 2 dipped in between. After the

maximal OD600 values is reached the values decrease continuously.

At 10 and 20 $\mu\text{g/mL}$ Puro concentrations, exponential growth begins with a notable delay of 4 to 7 days (10 $\mu\text{g/mL}$) and 7 to 8 days (20 $\mu\text{g/mL}$). In addition, at 20 $\mu\text{g/mL}$ one replicate (Cltr 2) shows no growth at all after 11 days. For 10 $\mu\text{g/mL}$ the max. OD600 is reached between 7 and 10 days, with maximum OD600 values ranging from 0.100 (Cltr 3) to 0.189 (Cltr 1). Afterwards the values decline continuously. Triplicates Cltr 3 and Cltr 1 of the 20 $\mu\text{g/mL}$ Puro preparation reached their maximal OD600 of around 0.14 on day 10. By day 11, a slight decrease in the OD600 values can already be observed.




Figure 8: Growth curve in DSM 1523 for *M. thauri* for various concentration of puromycin (Puro): 0 $\mu\text{g/mL}$, 1 $\mu\text{g/mL}$, 2 $\mu\text{g/mL}$, 5 $\mu\text{g/mL}$, 10 $\mu\text{g/mL}$ and 20 $\mu\text{g/mL}$. Experiment was performed in triplicates (Cltr. 1, 2 and 3), with each triplicate concentration series is inoculated with its own full-grown pre-culture. The OD600 of the pre-culture were 0.154 for Cltr 1, 0.173 for Cltr 2 and 0.120 for Cltr 3. The OD600 was plotted on a logarithmic scale against time. OD600 values less than 0.000 were set to 0.001. A non-inoculated DSM 1523 medium solution was used as a blank.

The growth curves of *M. thauri* for Puro concentrations of 0 and 1 $\mu\text{g/mL}$ reach their OD600 maximum after 3 days, similar to *M. boviskoreani* (Figure 8). However, the maximum does not exceed 0.3 and ranges from 0.103 (Cltr 1, 0 $\mu\text{g/mL}$) to 0.263 (Cltr 3, 1 $\mu\text{g/mL}$). After that, the OD600 decreases rapidly again, so that at 0 $\mu\text{g/mL}$, Cltr 1 and 2 already have an OD below 0.003 after 9 days, and Cltr 3 is also just barely above 0.01 after 10 days. For 1 $\mu\text{g/mL}$, the final measured OD values range between 0.001 and 0.05.

For 2 µg/mL puromycin, Figure 8 shows growth for all three triplicates, reaching its maximum on day 3. However, the increase in OD600 values is significantly lower. Thus, the maximum for Ctr 2 is below 0.03, for Ctr 3 below 0.1 and for Ctr 1 bit more than 0.1. This is followed by another decrease in the values, so that the final OD600 range between 0.001 and 0.03. For the other measured Puro concentrations, in contrast to *M. boviskoreani*, no growth above an OD600 of 0.003 was observed with one exception (Ctr 3 at 5 µg/mL) (Figure 7 and Figure 8). For Ctr. 3 at a Puro concentration of 5 µg/mL, an OD600 of more than 0.1 was measured on day 3, but this value dropped back to 0.003 by day 6.

Cycloserin

M. thaueri was successfully cultivated in DSM 1523 containing 200 µg/mL cycloserin (Cyc-Se.). Visual growth could be detected after 1 day.

4.1.5 Nucleotide-baseanalogica sensitivity test

Similar to the AB sensitivity test, a growth experiment was conducted for the base analogs 8-Azahypoxanthin (8-Aza) for *M. thaueri*, *M. boviskoreani*, *M. millerae*. One difference is that the base analogs do not dissolve in H₂O, so they were dissolved in dimethylsulfoxid (DMSO). Furthermore, different concentrations were selected: 0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL, and one with 1 mL DMSO. The OD600 was measured and plotted on a logarithmic scale against time (Figures 9 through 11).

8-Azahypoxanthin

In the absence of 8-Aza the max. OD600 of *M. boviskoreani* is reached after 3 to 4 days with exponential growth within the first two days (Figure 9), followed by a continuous decline with a final OD600 of just under 0.1 on day 13. The solvent control (DMSO), in which no base analogs were added but only 1 mL of the solvent DMSO, showed a different growth curve. Initially, none of the triplicates begin to grow. Instead, the OD600 values first decrease. On day 3, slight growth begins, reaching a maximum of 0.1 on days 4 to 6. Afterward, the values decline to approximately 0.03 on day 13.

At the lower concentrations of 8-Aza (100 and 250 µg/mL), *M. boviskoreani* in Figure 9 shows a growth curve shape more or less similar to that of the corresponding positive control. However, at 100 µg/mL 8-Aza, the maximum OD600 value is reached within 1 to 3 days, but it is approximately 0.1 instead of just under 0.3. For the 250 µg/mL preparation 0.1 is also the maximum OD600 value. Here, growth does not begin until 2 to 4 days later, so that the




Figure 9: Growth curve in DSM 1523 for *M. boviskoreani* for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) and one bottle with 1 mL DMSO as solvent of 8-Aza. Experiment was performed in triplicates (Cltr. 1, 2 and 3), with each triplicate concentration series is inoculated with its own full-grown pre-culture. The OD600 of the pre-culture were 0.096 for Cltr 1, 0.105 for Cltr 2 and 0.152 for Cltr 3. The OD600 was plotted on a logarithmic scale against time. OD600 values less than 0.000 were set to 0.001. A non-inoculated DSM 1523 medium solution was used as a blank.

maximum is not reached until day 7.

For the three remaining 8-Aza preparation lines (500, 750 and 1000 µg/mL) for *M. boviskoreani* an OD600 below 0.01 was measured during the first 4 to 6 days. Then there was an increase to an OD600 of 0.03, which remained constant until the final measurement day (day 13). An exception is Cltr 2 in the 1000 µg/mL 8-Aza preparation. This triplicate grows from day 3 to day 5 to an OD600 of 0.1, which then decreases slightly until the end of the measurement series.

M. thaueri growth curves are visualized in Figure 10. Except for the positive control (0 µg/mL 8-Aza), no growth could be detected. An exception here is the triplicate Cltr 3 in the DMSO sample. Here, an OD600 of 0.3 was measured on Day 2, but it dropped to 0.03 by




Figure 10: Growth curve of *M. thauri* for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) in DSM 1523 and one bottle with 1 mL DMSO as solvent of 8-Aza. Experiment was performed in triplicates (Cltr. 1, 2 and 3), with each triplicate concentration series is inoculated with its own full-grown pre-culture. The OD600 of the pre-culture were 0.125 for Cltr 1, 0.148 for Cltr 2 and 0.210 for Cltr 3. The OD600 was plotted on a logarithmic scale against time. OD600 values less than 0.000 were set to 0.001. A non-inoculated DSM 1523 medium solution was used as a blank.

the next measurement day (Day 4). In the positive control, slight growth of *M. thauri* was detected. However, the growth curve differs quite noticeably from that of the positive control for *M. thauri* in Figure 8. Furthermore, there is considerable heterogeneity among the individual triplicates. Cltr 1 begins to grow from the first day and reaches its maximum OD600 0.174 on day 9 (see Figure 10). By the end of the measurement, the OD600 decreases continuously to 0.1. Cltr 3 begins to grow on Day 8, reaching a maximum OD600 of approximately 0.151 on Day 12. Between Days 13 and 14, the last triplicate then begins to show slight growth, reaching an OD600 of 0.118 on Day 16.

M. millerae growth results are visualized in Figure 11. The positive control (0 µg/mL 8-Aza) and the solvent control (DMSO) have a similar curve shape for all triplicates, with the max. OD600 being reached on day three, followed by a continuous decline. However, the curves




Figure 11: Growth curve of *M. millerae* for various concentration of 8-Azahypoxanthin (8-Aza) (0 µg/mL, 100 µg/mL, 250 µg/mL, 500 µg/mL, 750 µg/mL, 1000 µg/mL) in DSM 1523 and one bottle with 1 mL DMSO as solvent of 8-Aza. Experiment was performed in triplicates (Cltr. 1, 2 and 3), with each triplicate concentration series is inoculated with its own full-grown pre-culture. The OD600 of the pre-culture were 0.366 for Cltr 1, 0.339 for Cltr 2 and 0.281 for Cltr 3. The OD600 was plotted on a logarithmic scale against time. OD600 values less than 0.000 were set to 0.001. A non-inoculated DSM 1523 medium solution was used as a blank.

differ in their OD600 values. The positive control reaches a maximum value of 0.3, while the solvent control does not exceed 0.1. This also results in a lower final OD600 measurement for DMSO of below 0.03 and for the positive control slightly below 0.1. Clear trends for the other samples are generally difficult to discern at first glance. However, most triplicates do not reach an OD600 higher than 0.1.

The 100 µg/mL 8-Aza generally follows the curve shape of the positive and solvent control, although triplicates Cltr 1 and 2 reach their maximum OD600 value on day 4 with a value around 0.15, while Cltr 3 does not exceed 0.05. For the 250 µg/mL concentration, the triplicates have a constant OD600 of approximately 0.03 since day 3, with Cltr 1 and 2 showing slight growth starting on day 7, reaching approximately 0.1 by the end of the measurement. The triplicates for Cltr 2 and 3 at the 500 µg/mL concentration show a constant OD600 value of 0.03 starting on day 3. For Cltr. 1, an OD600 of 0.1 was measured between Days 2

and 10, which increases to just under 0.3 by Day 13. The higher concentrated preparations (750 µg/mL and 1000 µg/mL 8-Aza) show for triplicate Ctrl 3 a constant value of 0.03 starting on day 2, similar to the Cltr 2 and 3 for 500 µg/mL. At 1000 µg/mL, the other two triplicates show a constant OD600 of just under 0.1 starting on day 3, while at 750 µg/mL, only Cltr 2 shows this value starting on day 3. The Cltr 1 triplicate in the 750 µg/mL solution shows a value of 0.03 on days 3 and 4, then increases to an OD600 between 0.2 and 0.3 by day 7. This value decreases slightly by the end of the measurement series.

DMSO

In general, all preparation with DMSO showed the tendency to be more vulnerable to turn red when taking a sample for photometric measurement. In addition, the decolorization also took longer than in the positive control or other experimental conditions without DMSO, for example sometimes over an hour. This interaction of DMSO with the DSM 1523 media was investigated more closely in the *M. thaueri* 8-Aza sensitivity experiment (Figure 10). Here, an extra preparation was prepared with just 1 mL DMSO added in the DSM 1523, but without inoculation (DMSO –, Figure 12).




Figure 12: Color differences with and without DMSO after 6 days of incubation. Image of various preparations for *M. thaueri* from the same triplicate (Cltr. 3). The positive control (0 µg/mL 8-Azahypoxanthin (8-Aza)) contains only the microbe (*M. thaueri*) in DSM 1523; 1000 µg/mL preparation 8-Aza *M. thaueri* and the named base analog; DMSO + *M. thaueri* and 1 mL DMSO; DMSO – also contains 1 mL DMSO but was not inoculated.

After the first few days of incubation, a difference in color was observable among the cultures. Specifically, the DMSO bottles exhibited a red color, in contrast to the yellow color of the other samples in the 8-Azahypoxanthin (8-Aza) measurement series for *M. thaueri*. This is illustrated in Figure 12 using selected samples from the triplicate Cltr. 3 after 6 days of incubation. The OD600 was also measured for DMSO, but showed no difference from the baseline OD600 values of the other samples ranging from 0.03 to 0.04.

4.1.6 *pac*-gene

The *pac*-gene in the initial plasmid (*pac_old*), that should have been taken for the transformation via conjugation of the archaea, showed a different aminoacids (AA) sequence to the original sequence (*pac_org*) from *Streptomyces alboniger* (see (a) in Figure 13). They differ in five AA on the C-terminal end (see (a) in Figure 13).




Figure 13: Aminoacids (AA) sequence of two *pac* genes and their crystal structures. (a) shows the AA sequence of the original sequence from *Streptomyces alboniger* (*pac_org*) as well as from the *pac* gene that was located in the plasmid originally intended for transformation (*pac_old*). The differing section is highlighted in red. (b) The projected 3D structure for *pac_org* calculated by AlphaFold. (c) The projected 3D structure for *pac_old* calculated by AlphaFold. The color of the structure in AlphaFold shows the confidence of the predicted structure: blue, very confident, light blue less and yellow not very confident.

These mutation led in AlphaFold to different crystal structures. In (b) of Figure 13 the original *pac* has an antiparallel β -sheet with a big loop on the right side of its structure. The *pac_old* ((c) in Figure 13) shows also an antiparallel β -sheet at this position, but it is longer and has a shorter loop. Interestingly is, in its prediction for this region is not so confident as before (color change between (b) and (c) in Figure 13).

4.1.7 Transformation via conjugation

Of the 28 preparations 3 preparation lines showed visual, sustainable growth after transferring it into new selective media containing 20 µg/mL puromycin and 200 µg/mL Cyc-Se. (highlighted red in Table B16). Although most of the preparation showed in the recovery media after some growth, but except these three preparations line in none of the other occurred growth in later transferred cultures and they grew untypically dense for a pure *Methanobrevibacter* culture. The 6.6A preparation, which was inoculated with *M. boviskoreani** (Table B16), on the other hand showed the typical precipitates for *M. boviskoreani*. The other two successful preparationlines 5.6A and 5.6B contained *M. millerae*.

All three successful preparation lines were inoculated with fresh grown *Methanobrevibacter* culture (*M. boviskoreani** and *M. millerae**) and all had as conjugation strain *E. coli* WM6026. On the other hand, they had different recovery times: two belong to the preparation that had a short recovery time of 4.5 to 5 h (5.6A and 6.6A), and one with a long recovery time 19.5 h (5.6B). Furthermore the OD600 of *E. coli* WM6026 for 5.6A and 5.6B was 1.24 and for 6.6A 1.79 (Table B16).

Specifically, within these three preparation lines, six cultures at different stages of the transfer process showed growth. 2 for 5.6B (1st and 2nd transfer), one for 5.6 A (1st transfer), and three cultures for 6.6A (1st and 2nd transfer plus the recovery culture). All six were transferred two more times, and the 1st and 2nd transfer of 6.6A were transferred a third time after 6 days. For all a similar behavior could be detected. The 2nd and 1st transfer of 6.6A grew very well while the others grew but not as dense. Sequencing of the 16S-DNA of archaea revealed for these six cultures, that the cultures contain the expected *Methanobrevibacter* species. The negative control of the used primers did not show any bands. The sequencing of bacterial 16S-DNA showed no sign of *E. coli* WM6026, but a contamination with *Staphylococcus epidermidis* (*S. epidermidis*). A negative check of the original used primer revealed also a contamination of them with *S. epidermidis*. Two new primer sets were used, that did not show a contamination in the negative control, the results are shown in Figure 14 (see "bac. 16S fresh" and "bac. 16S extra" lanes). Again a clear band appears at approx. 1000 bp, which was verified as *S. epidermidis* via 16S-Sequencing. The band thereby is pretty thick and tends to smear.

Figure 14 presents also the result for the PCR with a primer set (38 and 39, Table B7) for a 838 bp part of the suicide plasmid. All six cultures (lane 1 to 6 of the "Plasmid" lanes) show a clear band at 750 bp, which is a bit less thick as the 1000 bp band of the bacterial 16S-rRNA. For the lane 1,3 and 4, which belong to the three *M. millerae** (1st (lane 4) and




Figure 14: Gel image for different PCR products of growing cultures of *M. boviskoreani* and *M. millerae* after conjugation. For the lanes labeled 1, gDNA from culture 5.6B (1st transfer) was used; for 2, from 6.6A (1st transfer); for 3, from 5.6A (2nd transfer); for 4, from 5.6B (2nd transfer); for 5, 6.6A (2nd transfer); for 6, 6.6A (recovery). For a closer look at the cultures see Table B16. "Plasmid" displays the results of the PCR for a portion of the plasmid used in the conjugation. The expected size would be 838 bp. "bac. 16S fresh" and "bac. 16S extra" show both the PCR product for the bacterial 16S-rRNA. Thereby were different primers used, but both had a clear negativ control before. For "bac. 16S fresh" the primers were freshly aliquoted. For "bac. 16S extra" primers different from those used in the first 16S sequencing were used. As ladder the 1 kb ladder from ThermoFischer was applied ("1kb" lanes).

2nd transfer (lane 1) of 5.6B plus 1st transfer (lane 3) of 5.6A), there is a second smaller band slightly below 500 bp. Furthermore, is the band at 750 bp a bit smaller than the band of *M. boviskoreani** cultures. "Primer Blast" on NCBI did not reveal any off-targets with PCR products smaller than 4000 bp in the gDNA of *M. millerae*, *M. boviskoreani*, *E. coli* and *S. epidermidis*.

A full genome sequencing of the culture is still pending due to the contamination problems.

***E. coli* cultivation test in DSM 1523**

Cultivation of *E. coli* DH5 α was tested under similar settings in DSM 1523 as for *Methanobrevibacter*. Three drops for inoculation was enough to get a dense culture the next day.

4.2 Geography

4.2.1 National methane emission since 1990

Figure 15 shows the development of the total methane emission of a year as well as of the specific sectors from 1990 to 2020s for Germany (DEU), New Zealand (NZL) and United States of America (USA). The first thing that stands out is that the USA generally produces notably more CH_4 , what cumulates in a different scale than for the other two countries. The maximum total emission is 35 Tg CH_4 , while for DEU the maximum is 5 Tg and for NZL it is 1.5 Tg.




Figure 15: Time series of the anthropogenic methane emission of Germany (DEU), New Zealand (NZL) and United States of America (USA). The different relevant emission sectors are shown with their total sum (Total). Furthermore, the total emission minus the CH_4 produced in enteric fermentation (EnterFe) processes of cattle is plotted as well. Methane is plotted as Tg CH_4 of a year against the time.

For Germany, a clear downward trend is evident in total CH_4 emissions (Figure 15). Emissions fell around 3 Tg CH_4 in the 34 year long time series (1990 5 Tg to 2 Tg in 2024), representing a decrease of approximately 60 %. Two distinct phases of this trend can be identified: first, from 1990 to 2006, with a sharp decline of about 2.4 Tg CH_4 (approximately 2.6 Tg CH_4 in 2006), followed by a second phase with a more moderate decline of around 0.6 Tg to 2 Tg of anthropogenically produced methane in 2024. Total emissions excluding those from enteric fermentation (EnterFe) in cattle follow a similar trend, with the curve's value being around

1 Tg CH₄ lower (Figure 15 DEU).

Looking at the sectoral emissions of DEU, it becomes apparent that in 1990 there were three equally large CH₄-producing sectors: "Energy," "Waste," and "Agriculture," each accounting for approximately 1.5 Tg CH₄ (Figure 15). However, these sectors have developed differently. The "Energy" and the "Waste" sector have followed quite similar trends. Following a sharp decline between 1990 and 2006 - with the "Waste" sector not beginning to change until 1994 - from 1.5 to 0.5 Tg, a moderate decline then sets in, until approximately 0.025 Tg of CH₄ is emitted in 2024. Agriculture is also changing, though only very slightly compared to the other two sectors: from 1.6 Tg of methane in 1990 to approximately 1.25 Tg CH₄ in 2024, with the largest single change occurring between 1990 and 1991, amounting to a difference of about 0.1 Tg. So in 2024 the anthropogenic methane emission of Germany is dominated by the agriculture sector, which accounts for 60 % of the total emission. In addition to these three sectors, two others are shown in Figure 15 ("Industrial Processes & Product Use" and "LULUCF" (land use and land use change and forestry)). The "Industrial Processes & Product Use" sector is a negligibly small source of methane emissions. Its CH₄ emissions have remained consistently well below 0.1 Tg over the 35-year period. With CH₄ emissions consistently ranging between 0.3 and 0.4 Tg, the "LULUCF" sector was the fourth-largest single methane emission sector in Germany during the 1990s, but it surpassed the waste sector in 2016 and has been the second-largest CH₄-emitting sector in DEU after agriculture since 2019.

For the USA the distance between total methane emissions and total emissions excluding cattle EnterFe remains fairly constant at around 10 to 15 Tg CH₄ (Figure 15). In addition, a clear, steady decline can be observed for the total methane emission from 1990 (approx. 33 Tg CH₄) to 2022 (approx. 27 Tg CH₄), although the curve does not follow the trend linearly but rather fluctuates slightly. Over this 32-year period, the U.S. has reduced its methane emissions across all sectors by about 6 Tg CH₄, which corresponds to a reduction of 18 %. As in Germany, the three most significant methane-producing sectors in the U.S. are "Energy," "Agriculture," and "Waste" in 1990. However, here the "Energy" sector is the largest contributor, accounting for nearly half of the emissions in 1990 with 15 Tg CH₄, followed by the waste and agriculture sectors with approximately 8 Tg CH₄ each. The "Energy" and "Waste" sector show a downward trend over the time series (energy: from 15 to 10 Tg CH₄ and waste: from 8 to 5 Tg CH₄), while emissions from agriculture rise slightly over time, from 8.5 Tg to 10 Tg CH₄. Thus, in 2022, agriculture and energy - each at 10 Tg CH₄ - are the largest methane emission sectors and together account for more than two-thirds of total methane emissions in the U.S.

in 2022. Two other sectors contribute to U.S. methane emissions: the “Industrial Processes & Product Use” sector, which is relatively small and therefore negligible, and the “LULUCF” sector, with a constant range of 0.2 to 0.25 Tg CH₄.

Compared to the other two countries, New Zealand presents a different picture (Figure 15). First, total CH₄ emissions in 2024 are nearly the same as those in 1990, namely about 1.4 Tg CH₄. Furthermore, a slight increase in emissions to 1.5 Tg CH₄ can be observed through 2006, followed by a slight decline. Second, “Agriculture” is the absolute dominant sector in terms of methane emissions and accounts for nearly 90 % of CH₄ emissions from NZL (see Figure 15). All other sectors account for significantly less than 0.1 Tg CH₄ per year, with the exception of the waste sector, whose methane emissions are slightly above 0.1 Tg CH₄. Third, the difference between total methane emissions and total emissions excluding cattle EnterFe increases by about 60 % (0.5 Tg CH₄ in 1990 and 0.8 Tg in 2024).

4.2.2 Enteric fermentation processes of cattle

Methane emissions

Figure 16 shows the trend in methane emissions from enteric fermentation in cattle, as well as their subcategories “dairy cattle” and “non-dairy cattle” for each country.




Figure 16: Time series of methane emission derived from enteric fermentation processes in cattle and its subcategories dairy and non-dairy for the countries: Germany (DEU), New Zealand (NZL) and United States of America (USA). Methane emission are measured in emitted Tg CH₄. Emissions are calculated for dairy and non-dairy cattle with the indicators in Figure A4:A6 and the eq. (1). The cattle emission is than the sum of its subcategories.

Cattle emissions for Germany (DEU) decline from 1990 to 2024 (from 1.25 Tg CH₄ to approximately 0.8 Tg), with a steeper decline in the first year of the time series, followed by a more gradual decline (Figure 16). For dairy and non-dairy cattle, this initial decline is also evident in Figure 16, after which a slight decline can also be observed (dairy cattle: 0.75 Tg CH₄ in 1990 to 0.5 Tg in 2024; non-dairy cattle: 0.55 in 1990 to 0.35 in 2024). Dairy cattle are an exception: their emissions drop to 0.5 Tg CH₄ by 2006, then rise slightly again through 2015, and subsequently decline once more, returning to 0.5 Tg by 2014. Dairy cattle consistently produce slightly more CH₄ per year than non-dairy cattle (0.1–0.2 Tg CH₄, Figure 16). This contrasts with the population ratio shown in Figure A4, where the dairy cattle population size generally accounts for about half of the non-dairy cattle over the years. Further differences in the indicators are evident for Ym, where dairy cattle had a significantly higher value of 7 % in 1990 compared to 6.25 % in non-dairy-cattle, which, however, declines sharply to 6.1 % by 2024, while the value for non-dairy cattle rises to 6.5 %. GE changes similar, the value for the non-dairy cattle remains constant at 100 MJ head⁻¹ day⁻¹, while the value for the dairy cattle population rises from 250 to 380 MJ head⁻¹ day⁻¹. Furthermore, it stands out that the trend in emissions for cattle and its subcategories aligns quite well with the trend the corresponding population size (Figure A4).

Methane emissions from cattle in EnterFe for New Zealand rise from 0.5 Tg CH₄ in 1990 to 0.75 Tg in 2024, while the values have remained relatively constant since 2014. An increase is also evident for dairy cattle, which has plateaued since 2014 (0.25 Tg CH₄ in 1990 to 0.55 Tg in 2024). Non-dairy cattle, on the other hand, show similar values of around 0.5 Tg CH₄ in both 1990 and 2024. Thus, in 1990, dairy and non-dairy cattle contributed equally to methane emissions from the cattle population. However, this share has changed over the years for dairy cows, so that by 2024 they will account for about two-thirds of the emissions. This shift in the ratio is quite similar across the subcategory populations size (Figure A5). Furthermore, the GE values for non-dairy cattle remain constant at 150 MJ head⁻¹ day⁻¹, while the value for dairy cattle rises from 160 to 225 MJ head⁻¹ day⁻¹.

In the USA, methane emissions from dairy cattle rise from just under 2 Tg CH₄ to 2 Tg, with the slight increase not beginning until around 2005. Non-dairy cattle methane emission, on the other hand, fluctuates over the time period from 1990 to 2022 ranging from 4.9 to 5.5 Tg. This fluctuation is also visible for cattle, where the values range from 6.5 Tg CH₄ to 7.1 Tg (Figure 16). Unlike in the other two countries, non-dairy cattle here emit notably more than dairy cattle (2024: 5 Tg CH₄ versus 2 Tg). As with the other countries, the emission curves correspond fairly well with the change in population size from Figure A6, where non-dairy

cattle (80 million head) are kept in clear greater numbers than dairy cattle (20 million head). The curve for dairy cattle does not match the livestock numbers exactly, as these remain constant. However, the GE for dairy cattle rises steadily from 200 to 260 MJ head⁻¹ day⁻¹ between 1990 and 2022, while the Ym value decreases from 6.5 % to 6.1 % over the same period.

When comparing cattle emissions across countries in Figure 16, it is striking that the USA produced more than three times as much in 2022 as the other two countries combined (6.8 Tg CH₄ compared to less than 2 Tg combined). This is also reflected in the number of animals: in 2022, the US had approximately 100 million cattle, while DEU and NZL each had around 10 million (Figure A4 through A6). Germany and New Zealand produce similar amounts of methane from cattle farming in 2024 (approx. 0.8 Tg CH₄), in 1990, DEU had produced twice as much, but also kept twice as many cattle (approx. 20 million animals in 1990 compared to 10 million in 2024).

Share of CH₄ emissions from EnterFe of cattle

Figure 17 shows the share of methane emissions derived from enteric fermentation processes in cattle on the total amount of anthropogenic produced methane of a country and on the agriculture methane emissions.




Figure 17: Time series of the share of methane emissions resulting from enteric fermentation of cattle on methane produced in the entire agriculture sector and the total amount of CH₄ per country and year. The calculation of the share are based on the information of the reported CRT.

The share of CH₄ produced through EnterFe processes in cattle on entire amount of emitted methane for the agriculture sector declines slightly for Germany (approx. from 78 % 1990 to 76 % 2024, Figure 17) and USA (from 76 % 1990 to 74 % 2022, Figure 17). For the share on total methane emissions, both curves increase over time quite linear, but is the increase for the US mild from 20 % (1990) to 25 % (2024), is it for DEU quite intense from 1990 also a value of around 20-25 % to 45 % in 2024. New Zealand time series for the development of the share of enteric fermentation cattle CH₄ emission looks a bit different to those described (Figure 17). Both curves for the share on total and agriculture methane emission show a similar form, they just have slightly different values. The share on agriculture on the one hand grew from 1990 to 2024 from 45 % to 70 %, on the other hand the share for total emission from 40 % to a bit less than 65 %.

4.2.3 Reduction potential in enteric fermentation processes of cattle

Figure 18 shows the possible yearly average saved CH₄ for the decade from 2010 to 2019 in the countries NZL, DEU, and USA, if assumed that the mitigation strategy "immunization of cattle" would have implanted. For this purpose, five different scenarios of success were assumed and tested, ranging from a 10 % to 50 % microbiome shift towards non-methane-producing microbes. Table B17 in the appendix lists the precisely calculated amounts of saved CH₄ and CO₂ equivalent (CO₂-eq.).

In the 10 % microbiome shift scenario, the three countries would have saved together approximately 0.9 to 1 Tg CH₄ per year, with about 0.75 Tg attributable to the United States alone. At 30 %, the total reduction in methane emissions would be approximately 2.8, and at 50 %, it would be almost exactly 4.5 Tg. The rise between the different reduction scenarios seems to be linear in Figure 18, although Table B17 shows a slightly non-linear rise. Besides, for the various scenarios in Figure 18 it is obvious, that under identical scenarios, by far the largest amount of CH₄ can be saved in the United States, and that Germany and New Zealand make roughly equal contributions over the ten-year period examined, with Germany contributing slightly more.

For global warming potential (GWP), clear quantitative difference can be observed for the different time horizons. For example, the scenario 30 % microbiome shift approximately 220 Tg eq. CO₂ would be emitted less across all countries for a 20-year time horizon. Over a 100-year time horizon, this figure would be only 75 Tg. The relative dominance of the United States remains evident in these figures.




Figure 18: Saved CH₄ through different scenarios (10, 20, 30, 40 and 50 %) of a successful shift of rumen microbiome towards less methanogenic microbes. The saved methane is plotted as Tg CH₄ against the these five "Emission reduction scenarios" (CH₄). The values for the global warming potential (GWP) for 20 years (79.7) and 100 years (27) are plotted as well in Tg CO₂-eq. (IPCC, 2023a). The saved CH₄ is calculated as an average for the decade 2010-2019 for each country (Germany (DEU), New Zealand (NZL) and United States of America (USA))

4.2.4 Prediction for 2030

Figure 19 (DEU), 20 (NZL) and 21 (USA) show the total methane emission for each country as a time series from 1990 to the last published year in the CRT and beyond until 2030 as a forecast. In addition, the two global methane pledge emission targets for each country are shown in red, with the target of 30 % fewer total methane emissions than in 2020 represented as a triangle and the target of 40 % fewer emissions than in 2010 represented as a circle. The forecast was performed via three different linear models (using 5, 10, or 15 years as the reference period for the fit) and for a scenario in which no further intervention was made, as well as for three scenarios with varying degrees of success in cattle immunization (10, 30, and 50 % shifts in the rumen microbiome) (Section 3.2.5). Two things stand out when comparing

all prediction models across all three countries for total methane emissions. First, all models show a negative development, although the max. confidence intervall (CI) of the 5 year model for DEU has a positive trend. Besides, the forecast for the fit with 10 or 15 years as time reference show very similar prediction while the 5-year linear model differs a bit from them. While in DEU the 5-year fit predicts higher values for CH₄ production for 2030 than the 10- and 15-year model, for NZL and USA the 5-year model predicts lower values than the other two.




Figure 19: Historical values for total methane emissions in Tg for **Germany** from 1990 to 2024 and the forecast of methane emissions through 2030. The projection was generated using three different linear models with varying time reference periods (the last 5, 10, or 15 years), which are listed in Table B18 along with the corresponding equation and R². Total emissions were not extrapolated directly. Instead, they were determined using a prediction of total emissions excluding enteric fermentation in cattle, as well as the four indicators (DE, GE, NE_x, and population size), to calculate the missing emissions from cattle production. In addition to predicting total CH₄ emissions without additional mitigation measures (blue), the calculation was also performed for three reduction scenarios (10, 30, and 50 % shift in the rumen microbiome) (green). For each linear extrapolation, the confidence intervall are displayed as a colored area in the corresponding color (confidence level of 95 % was used). The two global methane pledge (GMP) CH₄ emission targets are also shown in red: 60 % of 2010 methane emissions as a circle and 70 % of 2020 methane emissions as a triangle.

Figure 19 visualizes the results of the prediction for Germany until 2030. Besides, the GMP emission goal for DEU are at 1.5 Tg and 1.4 Tg CH₄, where the higher emission value is for the 40 % less. The values for the combined CI of the three linear models are ranging from 1.4 Tg to 2.25 Tg CH₄, while the CI of the 5-year model (1.4 Tg to 2.25 Tg CH₄) is notably wider than the combined for the other two models (1.4 Tg to 1.75 Tg CH₄). A closer look at the models in Figure 19 show the five-year model predicts a nearly constant emissions trend with just a slight decline (from 1.9 Tg CH₄ to 1.8 Tg), although the confidence intervals here are quite wide and do show even a possible increase of methane emission. So the 5 year model predicts Germany does not reach their emission goals. The 10- and 15-year models, on the other hand, show a clear downward trend with a value of approximately 1.5 Tg CH₄ in 2030, which corresponds almost exactly to the 60 % target of the GMP.

The projected values for the reduction scenario 10 hardly differs from the scenario without mitigation measures and deviates by only about 0.1 Tg (Figure 19). A greater difference can be observed for Scenario 30. Here, the projected emissions for the 5-year fit would be roughly at the level of the GMP target of 40 % less than 2010 emissions and thus at values comparable to those in the 10- and 15-year models under “Projection without vaccination.” For this scenario, the values for these two models under “with immunization” are just below the target of 70 % of 2020 emissions, namely at approximately 1.3 Tg CH₄. The range of cumulative CI for the year 2030 extends from 1.1 Tg to just under 2 Tg of emitted CH₄. This means, for these models assuming a 30 % change in the rumen microbiome, no further increase in methane levels would be expected at least until 2030. The scenario 50 with an immunization of cattle that leads to a 50 % shift of microbiome towards less methane production, had an combined CI range from slightly below 1 Tg to 1.75 Tg CH₄ emitted in 2030. Where all three models would achieve both GMP emission targets for 2030 (Figure 19, with the 5-year model predicting a an emission of 1.4 Tg CH₄, although the CI partially exceeds the emission targets still.

Figure 20 shows the prediction for NZL. The prediction without immunization has a combined CI range from slightly above 1 Tg to 1.35 Tg emitted methane for 2030. Here, the CI is, as before for DEU, notable wider for the 5-year model as the other two. Neither the values directly predicted through the models (1.2 Tg CH₄ for the 5 year fit and 1.25 to 1.3 Tg for the 10- and 15-year model) nor the CI range achieves one of the two GMP emission targets. The 60 % of 2010 emissions is at 0.8 Tg and 70 % of 2020 at slightly below 1 Tg CH₄.

The difference between no immunization and immunization for the reduction scenario 10 is like for Germany in Figure 19 round about 0.1 Tg, and dose not help NZL to meet its




Figure 20: Historical values for total methane emissions in Tg for **New Zealand** from 1990 to 2024 and the forecast of methane emissions through 2030. The projection was generated using three different linear models with varying time reference periods (the last 5, 10, or 15 years), which are listed in Table B19 along with the corresponding equation and R^2 . Total emissions were not extrapolated directly. Instead, they were determined using a prediction of total emissions excluding enteric fermentation in cattle, as well as the four indicators (DE, GE, NE_x, and population size), to calculate the missing emissions from cattle production. In addition to predicting total CH₄ emissions without additional mitigation measures (blue), the calculation was also performed for three reduction scenarios (10, 30, and 50 % shift in the rumen microbiome) (green). For each linear extrapolation, the confidence interval are displayed as a colored area in the corresponding color (confidence level of 95 % was used). The two global methane pledge (GMP) CH₄ emission targets are also shown in red: 60 % of 2010 methane emissions as a circle and 70 % of 2020 methane emissions as a triangle.

emission goals certainly, although the minimum of the combined CI is right at the 70 % target (Figure 20). At the reduction scenario 30, this aim lays between the direct prediction of the 5-year (approx. 0.9 Tg CH₄) and the extrapolation with the 10- and 15-year model (1 Tg). Besides, the lower limit for the confidence interval reaches the other GMP aim. For the last assumed scenario (50 % shift of microbiome) the 10- and 15-year linear model predict methane emission values that are nearly exact the 60 % target. So, most of the predicted values for the methane emission achieves this GMP aim with values ranging from 0.7 Tg to

0.85 Tg emitted methane for the year 2030.




Figure 21: Historical values for total methane emissions in Tg for the **USA** from 1990 to 2022 and the forecast of methane emissions through 2030. The projection was generated using three different linear models with varying time reference periods (the last 5, 10, or 15 years), which are listed in Table B20 along with the corresponding equation and R^2 . Total emissions were not extrapolated directly. Instead, they were determined using a prediction of total emissions excluding enteric fermentation in cattle, as well as the four indicators (DE, GE, NE_x , and population size), to calculate the missing emissions from cattle production. In addition to predicting total CH_4 emissions without additional mitigation measures (blue), the calculation was also performed for three reduction scenarios (10, 30, and 50 % shift in the rumen microbiome) (green). For each linear extrapolation, the confidence interval are displayed as a colored area in the corresponding color (confidence level of 95 % was used). The two global methane pledge (GMP) CH_4 emission targets are also shown in red: 60 % of 2010 methane emissions as a circle and 70 % of 2020 methane emissions as a triangle.

For the U.S., the 10- and 15-year models for "prediction without immunization" in Figure 21 predict an emissions value for 2030 that corresponds almost exactly to the 2022 value (approximately 27 Tg CH_4). Here the maximum of the CI even shows an increase in the emission values, although they do not predict a positive slope. The 5-year fit, on the other hand, shows a clear decrease by 2030 with a reduction of approximately 4 Tg CH_4 from 27 Tg in 2022 to 23 Tg of methane emitted in 2030. Even with the combined CI range (22 to 28 Tg CH_4), the

lowest value is still notably higher than the nearest GMP emissions target. Here, the 70 % of 2020 total methane emission is at 20 Tg CH₄ and 40 % less than 2010 is at approx. 18.5 Tg. Even the confidence interval range of reduction scenario 10, which differs by approximately 1 Tg from the scenario with no additional mitigation efforts, does not meet this target with its lowest value of approximately 21 Tg emitted CH₄ in 2030. With reduction scenario 30, the predicted value of 21 Tg CH₄ for the 5-year model is still slightly above the 70 % target, but the minimum value of CI range meets this target at least. The maximum value for the CI range is approximately 26 Tg, meaning that under this scenario, no values predicted for the year 2030 are above the 2022 value (see Figure 21). In the 50 % reduction scenario, the 5-year model prediction, with a value of approximately 19.5 Tg CH₄, is slightly below the 70 % target but still above the GMP's 60 % goal. However, the CI range of the 5-year fit from 18 to 21 Tg CH₄ meets this target. The other fits, as well as their CI range (21 to 24 Tg CH₄), do not meet either of the two GMP targets even in reduction scenario 50 (Figure 21).

Two points stand out when comparing Germany with the other two countries (Figure 19 to Figure 20 and 21). First, in Germany, the predicted range of emission values at least partially meets the two emission targets set by the global methane pledge (GMP), whereas in the other two countries, the emission values exceed the targets. Second, the value for the 60 % of 2010 emissions target is higher than the 70 % of 2020 emissions target for DEU. For the other two countries, it is the other way around. Even so, the two values are in a similar range for all of them.

5 DISCUSSION

5.1 Biochemistry

5.1.1 Transformation via conjugation

Promising initial results have been achieved for implementing the first genetic toolbox for *M. boviskoreani* and *M. millerae*, even though a final assessment by whole genome sequencing is still pending (see Section 4.1.7). The transformation of *M. thaueri* was not successful. Three cultures in two preparation lines for *M. millerae* and three cultures in one preparation line for *M. boviskoreani* (Table B16) were tested positive by PCR to taken up plasmid-DNA (Figure 14), although the shown band is a bit lower than expected. The positive result could be due to four other reasons.

First, the plasmid could still be present in the media and be extracted along with the gDNA. This scenario is maybe likely for the recovery culture but for the 1st or especially the 2nd transfer, where only 1 % is left of the recovery culture, this seems to be unlikely. Second, the plasmid is amplified through *E. coli* through the corresponding ORI on the plasmid, but the bacterial 16S-Sequencing revealed no contamination with *E. coli* although *Staphylococcus epidermidis* was detected (Figure 14). For this species the plasmid contains no ORI. Third, the primers have an off-target with a similar sized product in the gDNA of present microbes in the culture, which was disproved by a search using “Primer Blast” on NCBI. Fourth, it could be due to an unlikely contamination of the primer set with the used plasmids, but this can not be ruled out due to a missing negative control.

To have final clearance a whole genome sequencing is needed. The problem is, why the whole genome sequencing can not be performed right now, is the revealed contamination with *S. epidermidis* via bacterial 16S-Sequencing. Because of that, the next step would be to purify these cultures through plating on selective media and picking a single colonie for the following analyses. If whole-genome sequencing confirms that the plasmid has been successfully integrated, the next step would be to test the counter-selection implanted in the plasmid design using 8-Azahypoxanthin. Also, it would be interesting to test if other transformation methods as electroporation could work.

Based on the comparison of the six successfully growing cultures, some factors influencing the conjugation can be assumed, although a rather small sample was investigated here and, to verify this, further investigation is definitely needed.

First, the growth status of *Methanobrevibacter* seems to be relevant. Growth only occurred among the 16 of overall 28 preparation lines that used freshly grown cultures (Table B16). This aligns with the literature, where cultures from late exponential or early stationary phase were used for successful transformation (Capovilla et al., 2025; Fink et al., 2021). This could also be the reason why the transformation of *M. thaueri* did not work, since only an old culture was used for this strain. The actual growth phase of the initial cultures used cannot be determined here, due to missing OD600 values for the *Methanobrevibacter* cultures. This should be addressed in future investigations.

Second, all three growing preparation lines used *E. coli* WM6026 as the donor strain for the interdomain conjugation. Future transformation attempts with *M. boviskoreani* and *M. millerae* should focus on this. The methylation pattern of *E. coli* WM6026 therefore does not impact the transformation of *M. boviskoreani* and *M. millerae* (Schwalen et al., 2018, SI).

Third, the recovery time is not as critical for the success of the transformation as described for *Methanothermobacter thermautotrophicus* ΔH in Fink et al. (2021). In addition, no direct trend is detectable for the OD of *E. coli* WM6026 in this preparation set, although an OD range of 1.24 to 1.79 seems to work.

To improve the conjugation protocol further, it would likely be useful to first test whether a specific growth phase of *Methanob.* has an effect by measuring its OD600 beforehand, because a clear trend towards fresh grown cultures is already visible for this conjugation experiment. To determine whether the OD600 of *E. coli* WM6026 influences success or whether the ratio of *E. coli* cells to archaea cells does, as already described as a critical factor in Kopp et al. (2004) for the conjugation of *Sorangium cellulosum*, further test series must be conducted. Here, OD600 measurement of the used *Methanobrevibacter* cultures is needed as well.

5.1.2 Plasmid constructs

An interesting discovery was made while constructing the plasmids for transformation: the aminoacids sequence of the *pac* gene, which was on the parent plasmid and originally planned to be on the new constructed ones for the conjugation, differs in 5 aminoacids from the originally aminoacids sequence *Streptomyces alboniger*. This resulted in a different structure prediction by AlphaFold (Figure 13), which, according to Kryshtafovych et al. (2021), is expected to be as accurate as experimentally determined structures. Interestingly though, this differing sequence was used in the literature as the aminoacid-sequence of *Streptomyces alboniger* (Lacalle et al., 1989). If the changed protein-structure really has an influence on the

function or the performed conjugation is not clear. To answer this question it needs further investigation. Just to be on the safe side, for the used plasmids in the conjugation *pac* gene was replaced with the codon optimized original *pac* from *Streptomyces alboniger*.

In general the constructed plasmids followed the scheme in Figure 2, where the selection of a successful conjugation works with a resistance against puromycin via *pac*-gene and a counterselection with a sensitivity against 8-Azahypoxanthin (8-Aza). If the whole-genome sequencing proofs the success of the transformation, a next step for the plasmid experiments would be to test the other planned plasmids with a different promoter (*PglnA* instead of *hmtB*, see Table B15).

5.1.3 Sensitivity tests

Puromycin

Since the selection of successfully transformed *Methanobrevibacter* is based on resistance to puromycin (Puro), it was first necessary to determine whether, and at what concentration, *M. boviskoreani*, *M. millerae* and *M. thaueri* are sensitive to this antibiotic. *M. thaueri* is sensitive to puromycin at a concentration at 10 µg/mL and showed no spontaneous resistance within 10 days. *M. boviskoreani* is also sensitive at a concentration of 10 µg/mL, but 20 µg/mL enhances the time until spontaneous resistance occurs. However, at 20 µg/mL spontaneous resistance occurred after 8 days. Hence, cells have to be collected within this time span.

Puromycin can be used as a selection for transformed *M. boviskoreani* and *M. thaueri*, although they are a bit less sensitive than other archaea species described in the literature with, according to Mondorf et al. (2012) and Possot et al. (1988), a minimum inhibitory concentration (MIC) of 2 µg/mL for *Methanococcus voltae* and 5 µg/mL for *Methanosarcina mazei*. For the upcoming conjugation experiments, a concentration of 20 µg/mL puromycin was chosen for selection. Should growth occur within 8 days, it can be assumed that this was mediated by the introduced resistance and not due to spontaneous resistance.

8-Azahypoxanthin

The markerless mutagenesis is based on the counterselection with 8-Azahypoxanthin (8-Aza), therefore *M. boviskoreani*, *M. thaueri* and *M. millerae* has to be sensitive towards the base analogue. Although the *hpt* gene on the plasmid already provides a backup mechanism that induces artificial sensitivity to 8-Aza, as suggested in Klein et al. (2025). The sensitive experiment testing concentrations ranging from 100 to 1000 µg/mL 8-Aza have little to no informativeness, due to the discovery of a sensitivity towards the solvent of 8-Aza dimethylsulfoxide

(DMSO) (Figure 9 through Figure 11).

However, for *M. boviskoreani* a sensitivity is detectable for concentration of 500 µg/mL based on a two days delayed growth start and around 0.7 lower maximal OD600 values (Figure 9). *M. millerae* growth results do not allow a clear conclusion due to heterogenous growing through the different concentration preparation as well as between the triplicates (Figure 11). Nevertheless, the fact that all samples exhibit similar inhibition at the maximum concentration compared to the positive control may indicate that, even though the 100 µg/mL solution contains ten times less DMSO in the medium than the DMSO preparation, 8-Aza also inhibits growth here. What argues against this, however, is that no stronger inhibition is observed at higher 8-Aza concentrations, even though the DMSO concentration and base analog concentration increase. *M. thaueri* is very sensitive against DMSO and showed no growth at all except the positive control (Figure 10).

A plausible explanation for the negative effect of DMSO on the growth of *Methanob.* species is that, as reported in Atcher and Alfonso (2013), DMSO acts as a mild oxidizing agent toward dithiols at room temperature. Therefore, DTT, which is added to the culture as a reducing agent to remove residual oxygen and keep the medium anaerobic, reacts with the DMSO to form its cyclic structure with a disulfide bridge, whereas DMSO reacts to form dimethyl sulfide (Sanz et al., 2002). Consequently, no reducing agent is present in the medium, and the anaerobic cultures are exposed to greater oxidative stress.

This hypothesis is supported by the following: First, when samples were collected for photometric measurements, the cultures containing DMSO turned red more quickly and also took longer to lose their color than the positive controls (Section 4.1.5). Second, in the *M. thaueri* measurement series, one preparation contained only 1 mL DMSO and was not inoculated. Within a few days, this preparation culture turned distinctly red and did not fade (Figure 12).

However, this also means that the *Methanobrevibacter* themselves can partially reduce the solution, since in this case the cultures did not turn red as quickly or as distinctly as in the pure DMSO control, although they contained DMSO as well. But the *Methanobrevibacter* do not appear to be able to fully compensate for the absence of DTT, resulting in inhibited growth.

In the future, an alternative solvent should be sought or the counterselection can not be performed properly. In the literature Olson and Lynd (2012) state 50 mg/mL 8-Azahypoxanthin is dissolvable in 1 M NaOH or KOH. A possible problem here could be the influence on the pH of the media, the effect of this on the growth of the *Methanobrevibacter* has to be investigated.

5.1.4 General characterization of *Methanobrevibacter*

Besides the experiments leading to the first attempt to transform *M. thaueri* and *M. boviskoreani*, general characterization experiments were performed to improve our understanding of the *Methanobrevibacter* species in the rumen of cattle.

Cultivation

In this bachelor thesis the *Methanobrevibacter* species could be cultivated successfully in DSM 1523 and 119, which do not contain any rumenfluid, as is usually the case (Lee et al., 2013; Li et al., 2023; Miller & Lin, 2002). Because there was no visible difference between the cultivated cultures in these two media, most of the experiments were performed in DSM 1523, which is easier to handle since it does not contain the toxic fatty acid mix and the sludge fluid. In general, *Methanobrevibacter* reach their growth maximum within 2 to 4 days with a maximum at 0.3, that does not exceed 0.4. For calculating general growth parameter as generation time or growth rate further growth experiments are needed with a higher time resolution, especially in the exponential growth phase. The detected growth rate is as fast as described in the literature for other archaea, but here the *Methanobrevibacter* do not grow as dense, in some cases reaching only about one-third of the optical density reported by Hoedt et al. (2016) and Li et al. (2023).

A closer look at *M. boviskoreani* reveals that it grows quite reliably in the described manner and can also be easily spread plated. The only unusual aspect is the formation of precipitates (Figure A1), which makes photometric measurements somewhat more difficult. In this case, it is important to homogenize the culture as thoroughly as possible beforehand, even if the precipitates cannot be completely dissolved. Interestingly though, this behavior is not described for the type strain (JH1^T) of this species and also the other investigated *Methanob.* species did not show this. Why *Methanobrevibacter boviskoreani* AbM4 precipitates remains unclear.

M. thaueri, on the other hand, grows much more unreliably, as a higher heterogeneity in the time point of growth onset and growth density could be observed both within triplicates and between experiments. In addition, *M. thaueri* lyses fairly quickly after reaching maximal growth, so that within 4 to 6 days the culture density is low enough to appear visually clear of cells. Furthermore, spread plating on DSM 1523 (1.5 % agar) and pour Plating with DSM 119 (1 % agar) were not successful (Figure 5 and A3). The roll plating was successful but with a notable lower Plating efficiency than *M. boviskoreani* and *M. wolinii* (Table 5). This growing behavior of *M. thaueri* makes it more difficult to analyse it and especially to transform it, where the *Methanobrevibacter* culture should grow within two or three days. Thus, *M. thaueri*

does not appear to be suitable for basic research due to its unreliable growth.

Future research should further investigate whether *M. boviskoreani* and *M. thaueri* can use a liquid substrate as an alternative to H₂, allowing upscaling of growth experiments through the potential use of a plate reader. In contrast to the literature (Li et al. (2023) stated that *M. boviskoreani* JH1^T could use EtOH as a substrate), *Methanobrevibacter thaueri* CW^T and *Methanobrevibacter boviskoreani* AbM4 did not use EtOH as an alternative. Another substrate that some *Methanobrevibacter* can use is formate, which should therefore be tested next (Hoedt et al., 2016; Li et al., 2023).

Cellcount per mL

For the first time cellnumber per mL was determined for *M. boviskoreani*, *M. millerae*, *M. thaueri* and *M. wolinii*. Compared to the cellcount per mL for *E. coli* ($8 \cdot 10^8$ cells/mL) at a OD600 of 1 given by Merck KGaA (2026) the counted cells/mL for the *Methanob.* cultures are quite high (e.g. *M. wolinii*: $10.819 \cdot 10^8$ cells/mL at a OD600 of 0.387; Table B14). Since only one or two cultures have been counted for these organisms so far, further investigation are needed to verify these and investigate the relationship between cellnumber and OD600.

Besides the small data sample, two further factors contribute to the increased uncertainty. First, the chamber depth of 0.1 mm (LO - Laboroptik GmbH, 2026) caused cells to appear in multiple focal planes, increasing the risk of overlooked or double-counted cells. Second, the still small size of the cells at a 400x magnification plus the tendency to form chains or clumps, increase the risk of overlooked or double-counted cells further due to the problem to distinguish the cells from one another (Figure A2).

One approach to mitigate this risk was to count approximately 150 to 250 cells per large square, rather than fewer than 150, thereby reducing the relative impact of individual miscounts. This, of course, led to an increased workload. Further approaches could utilize the intrinsic fluorescence of methanogenic archaea (Lambrecht et al., 2017) and perform the counting using fluorescence microscopy. This would make it easier to identify the small *Methanob.* cells at 400x magnification.

Roll plating

In general, the technique works well for *M. boviskoreani*, *M. thaueri* and *M. wolinii*. For *M. boviskoreani* and *M. wolinii* less starting material should be used next time, since there were too many colonies, which are consequently too small for selective picking (see Figure 6 and Table 5). This also leads to a disclaimer, it is not proven through sequencing that the right

Methanobrevibacter grew, but the constant consumption of the H₂/CO₂ atmosphere proves there was definitely anaerobic growth. Still this plating technic has the potential to be a time saving alternative to the spread plating due to less work inside of the glove-box. But it needs improvement for a fitting quantity, so less but bigger colonies grow.

The plating efficiency shown in Table 5 are very low, with values in the lower two-digit ppm range, and even below 1 ppm for *M. thaueri*, while Apolinario and Sowers (1996) reached an efficiency above 50 % for other archaea species. However, the calculated plating efficiency in this bachelor thesis should be interpreted with caution, since the OD600 of the initial solution was not measured. Instead, it was assumed retrospectively that the cultures have a similar OD to those obtained by cell counting. For future determinations of plating efficiency, it would be important to measure the OD600 in advance and to plate only at an OD600 corresponding to those in Table 4.

5.2 Geography

5.2.1 Evaluation of immunization of cattle" as a mitigation strategy

As outlined in Section 2.2.3 two reference data are used for the assessment of the potential impact of the mitigation strategy "immunization of cattle". On the global scale the growth rate of methane (20.9 Tg/year) for the decade 2010 to 2019 (Saunio et al., 2025). On the national scale, the emission targets of the global methane pledge (GMP) to reduce the national emission about 30 % compared to 2020 methane emissions and 40 % to 2010 (Appelhans et al., 2025). DEU, NZL and USA signed the GMP.

National scale

For the evaluation of whether mitigation of methane production in the enteric fermentation processes of cattle can be an important missing piece in achieving the signed emission targets, CH₄ emissions had to be predicted for the year 2030. As described in Section 4.2.4, total emissions were predicted without any additional mitigation, as well as for different success scenarios of shifting the microbiome of cattle towards less methanogenic archaea. For this purpose, predictions were performed via three linear models using different time samples as reference: the last 5, 10, and 15 years. Figure 19 (DEU), 20 (NZL), and 21 (USA) show that the results of the 10- and 15-year models are quite similar, while the 5-year model usually differs somewhat more. This is likely due to the smaller data sample of the 5-year model, making it more susceptible to changes occurring in the most recent five years. By examining the trends in national methane emissions for individual sectors (see Figure 15), the linear

models for each country can be evaluated.

For DEU (see Figure 19), it can even be concluded that the 5-year model, predicting a lower methane emission reduction than the other two models (23.5 Tg to 26.5 Tg CH₄), is likely the most plausible. This can be explained by the fact that in DEU, the energy and waste sectors have remained largely unchanged over the past six years of the dataset (2018–2024), and since emissions are already at a low level, there is little room for further reduction (see Figure 15). From 1990 to 2018, CH₄ emissions from these two sectors decreased continuously. This is still factored into the 10- and 15-year models, leading to predictions with a stronger decrease. For NZL (Figure 20) and USA (Figure 21), no such clear attribution can be made. However, the 5-year model can be described as optimistic in both cases, as it assumes that the sharper reduction in methane levels observed over the past few years will continue at this rate. The 10- and 15-year models, on the other hand, are somewhat more pessimistic, as they reflect periods of several years with stronger reductions in the past, which were subsequently followed by years of stagnant methane emissions or even slight increases.

For the three reduction scenarios tested in Figure 19, 20, and 21 - a 10 %, 30 %, and 50 % microbiome shift in the rumen towards less methanogenic archaea - it can be said that the 10 % scenario has too little impact in all three countries to help reach the targets, if these have not already been achieved. The latter case only applies to the 10- and 15-year models of DEU. Therefore, further mitigation of methane emissions is needed in DEU, NZL, and USA, either to enable these countries to meet their emission targets at all, or, in the case of DEU, to ensure that they are met. The 30 % reduction scenario ensures that NZL and DEU would meet at least one of the two reduction targets across all models, although their CI might not fully achieve the emission goals. For NZL, this refers to a 30 % reduction in national methane emissions in 2030 relative to 2020, and for DEU, a 40 % reduction relative to 2010. The fact that, for DEU, the 40 % reduction relative to 2010 target corresponds to a higher emission level than the 30 % reduction relative to 2020 target, whereas the opposite holds true for the other two countries, can be explained by a stronger decrease in methane emissions between 2010 and 2020 for DEU, while total emission values for the other two countries remained nearly stable during this period. The 50 % reduction scenario would even be sufficient for these two countries, with all models and their CI falling below both emission targets (Figure 19 and 20).

The situation differs somewhat for the USA. In none of the scenarios do the pessimistic models (10- and 15-year) meet either of the two emission targets of the GMP (see Figure 21). The optimistic model (5-year) would come close to the 70 % target under the 30 % reduction scenario and fall short of it under the 50 % reduction scenario, but would still meet the 60 %

target relative to 2010. This difference between countries can be attributed to the differing sectoral composition of national emissions (Figure 15). While agriculture was the main CH₄ source for DEU and NZL in 2024, in the USA, energy and agriculture contribute equally, and waste, though smaller, still has a substantial impact.

Two conclusions can thus be drawn. First, if the agriculture sector, and therefore EnterFe, is not the dominant methane emission source for a country, addressing it alone will not be sufficient to achieve the GMP targets. For example, in the USA, cattle emission reductions could only become the missing piece to meet the GMP emission goals if the reduction observed in the energy and waste sectors over the past five years continues at a similar rate. However, if efforts to reduce methane emissions from the energy and waste sectors were intensified, the need for cattle mitigation measures might initially be limited. Second, if agriculture is the dominant sector, there appears to be a need for new mitigation options to meaningfully reduce methane production, as agricultural emissions did not change substantially in any of the three investigated countries (Figure 15). CH₄ emissions derived from enteric fermentation in cattle appear to be a valid target for this, provided the reduction achieved is around 30 % or more.

Global scale

On the global scale several things gets quit obvious, if you compare the possible yearly averaged saved methane emission for the different reduction scenarios for the decade 2010-2019 (Figure 18) with the yearly growth rate (20.9 Tg CH₄) calculated in Saunois et al. (2025) for the same decade.

First, no reduction scenario (10, 20, 30, 40, or 50 % shift in the rumen microbiome) would have been sufficient to offset the annual growth rate. This is also true when the savings from all three countries examined are combined. Thus, neither changes in a few countries nor emission reductions in individual sectors are sufficient to stop methane accumulation in the atmosphere or even to enable a decrease in global methane levels. Nevertheless, a reduction scenario of 30 in the three countries (approx. 2.75 Tg CH₄) alone could have offset over 10 % of the global growth rate. Under reduction scenario 50, this figure would even be just over 20 % at 4.5 Tg CH₄. Considering that climate change and rising temperatures are causing natural CH₄ sources to become increasingly active, a prominent example being the thawing of permafrost (Saunois et al., 2025; Schädel et al., 2026; Turetsky et al., 2020). This means the budget for anthropogenic methane gets relatively smaller if CH₄ should not accumulate in the atmosphere. Therefore, efforts to reduce methane emissions from cattle should aim for a reduction of at least around 30 % in order to make a notable contribution to mitigate climate

change.

The second part of the Figure 18 underlines again with the calculation of CO₂-eq., that methane reduction really can be a short-term solution to soften climate change impacts and allow so to adapt/ mitigate further. So would the saved methane emission for the reduction scenario 30 (2.75 Tg) on a time horizon of 20 years correspond to 220 Tg CO₂, for a 100 year time horizon 75 Tg CO₂. The CO₂-eq. for the GWP20 would be roughly the same as the total CO₂ emission of Spain (220.08 Tg CO₂) for the year 2024 (European Commission. Joint Research Centre., 2025).

Finally, it is noticeable in Figure 18 that the amount of methane saved increases linearly with the scenarios. In the scenarios, two values are varied: first, methane conversion factor (Y_m), which has a linear relationship with methane emissions (see eq. (1)), and second, digestibility of food (DE), which has a nonlinear mathematical relationship with methane emissions (see Section 3.2.4). Although the theoretically assumed increase in dietary efficiency leads to further reductions in CH₄ emissions, this component is almost negligible because of the non-visual impact, so it has virtually no relevance to the significance of the method as a mitigation strategy.

Comparison with other mitigation strategies

Another mitigation strategy is the use of food additives, which also affect methanogenic archaea. For example, halogenated methane compounds such as bromoform inhibit the key enzyme (methyl-coenzyme M reductase) involved in methanogenesis (Boadi et al., 2004; Garnett & Eckard, 2024; Malyugina et al., 2025). In this context, the addition of red algae such as *Asparagopsis taxiformis* in in-vivo experiments with beef cattle resulted in an up to 80 % reduction in methane production (Malyugina et al., 2025, Table 4). However, even aside from this best-case scenario, reductions of over 30 % were regularly achieved in-vivo. To be competitive, the immunization strategy should also aim to achieve at least a 30 % reduction.

An advantage of immunization over feed additives is that it does not require daily administration to the animals and can be easily used in grazing animals, whereas feed additives are more difficult to implement in this context because the animals are not fed continuously or there is no controlled feed composition (Baca-González et al., 2020; Malyugina et al., 2025).

5.2.2 Characterization of national emission

The composition of the methane emission from the different sectors for the countries DEU and USA fits the described global pattern in the Section 1 and literature (Appelhans et al.,

2025; Mundra & Lockley, 2024) well (Figure 15). So they had both three dominant methane emission sources in 1990: the energy, waste and agriculture sector. The time series (Figure 15) shows for DEU clearly, methane emissions from the energy and the waste sector can already be reduced very effectively using current methods. So that in 2024 the emissions from those two sectors can hardly be reduced any further due to the low emission levels. This reduction trend is also evident for the USA, albeit to a lesser extent. Although it must be noted here as a disclaimer for the strong reduction in DEU, the reduction in the energy sector was achieved partly by outsourcing energy production or coal extraction to other countries, which reduces emissions nationally but not globally (Appelhans et al., 2025). At the same time, as shown in Figure 15, the challenge of reducing emissions from the agriculture sector remains particularly striking (Edelenbosch et al., 2024; IPCC, 2022a). New Zealand also shows only minor changes in the agricultural sector. However, over the entire period under consideration from 1990 to 2024, there is no other relevant CH₄ emitter besides agriculture. This clearly demonstrates that there can be notably national differences, which must be taken into account when assessing the significance and application of methods. Thus, for the United States, it is likely initially easier and more relevant to reduce emissions from energy and waste.

These national differences are also evident in the share of EnterFe CH₄ emissions from cattle relative to total national emissions in Figure 17. Thus, CH₄ from enteric fermentation processes in cattle is a major and relevant single source in all three countries. However, in the USA in 2022, it accounted for only 22 % of total emissions, whereas in DEU it accounted for just under 50 % and in NZL as much as 60 %. It can, nevertheless, be noted that EnterFe from cattle is a good single methane emission target for the three countries examined.

When examining cattle emissions from enteric fermentation (Figure 16) for the three countries, it is striking that the globally described increase in cattle emissions due to rising demand for animal products (Appelhans et al., 2025; FAO, 2009) is only slightly observable. For DEU there is even a decrease in emissions detectable. This is due to the fact that only OECD countries were considered. The described increase in demand and emissions is primarily attributable to non-ANNEX-I countries.

Furthermore, a comparison with the trends in cattle population numbers in Figure A4, A5, and A6 shows that the amount of methane emissions from cattle correlates very strongly with changes in population size. In addition, DEU shows that while increased production through higher-performing animals has led to an increase in GE, the simultaneous reduction in the number of animals has, nevertheless, resulted in a reduction in methane emissions (Appelhans et al., 2025; Niebuhr et al., 2026). However, this method of reducing population

size and methane emissions cannot be continued indefinitely, and there is also the question of to what extent animal welfare is still ensured in these high-performance animals (Appelhans et al., 2025). It can therefore be concluded that population size is the decisive factor for methane production in cattle farming.

5.2.3 Future steps

For the geography site next steps to improve the calculation and rating would be to check if shifting the microbiome of the rumen can have an influence on other emission sources or is cross-linked to other emission sources. One realistic option here is the manure management. From the calculation described in IPCC (2006b) one value already seems to be promising, the B_0 . B_0 is needed for the calculation of the EF for manure management. The value represents thereby maximum methane production from the manure produced by an animal category. This could be influenced by a different ratio of methanogen to non-methanogen anaerobic microbes. But this values has to be measured, so this hypothesis, therefore, can only be tested once the first successful applications of immunization have been made.

In addition, right now, just the gross effect was investigated off methane and its reduction in cattle. So could a counter effect be that the cow and shifted rumen microbiome produce less CH_4 but more CO_2 , so the shown saved carbon dioxide in Figure 18 could be less. If the immunization strategy is in the in-vivo state, this definitely needs to be checked. Furthermore, it would be interesting to extend the calculations to other countries in order to better assess the impact of such a strategy on a global scale. Of particular interest here would be countries that are not ANNEX-I states, in contrast to the three examined so far, although differences in emission patterns were already evident in those countries as well (see Section 5.2.2)

6 CONCLUSION

The interdisciplinary approach of this bachelor thesis to unit the small scaled investigation of the biochemistry with the greater view of the geography allowed a more holistic view towards the problem of hard-to-abate methane emissions from the agriculture sector.

The analyses of the national methane emissions for the three countries of interest (Germany (DEU), New Zealand (NZL) and the United States of America (USA)) showed that the agriculture sector, and therefore the emissions resulting from enteric fermentation processes mainly in cattle, are a big potential source for reducing methane emissions. For Germany and New Zealand is agriculture the only sector left for potential relevant methane reduction (see Figure 15).

The general geodata analyses of the national methane emissions from DEU, NZL and USA proofed the assumption derived from global methane emission pattern, there is a need for a fitting mitigation strategy toward CH₄ emission from enteric fermentation processes in cattle (Appelhans et al., 2025; IPCC, 2023a; Saunois et al., 2025). In addition, this single emission source contributes that much to the national emission (from 25 % in the USA 2022 to 45 % in DEU and 60 % in NZL, Figure 17) it will have a relevant impact on mitigate climate change, if international addressed. Especially the calculation of the global warming potential (GWP)₂₀ and GWP₁₀₀ in Figure 18 showed clearly, methane reduction could be really helpful short-term to stay at least below the 2 °C aim of the UNFCCC (2015). For this purpose, as already pointed out in Section 5.2.1 a shift of the rumen microbiome towards non-methanogenic microbes needs to be at least at 30 %. If the immunization of cattle can be helpful for this short-term mitigation, depends on the stage of biochemist development and investigation of a potent and specific vaccine against methanogenic archaea.

The biochemistry part of this bachelor thesis, could collect several basic information on the poorly understood genus *Methanobrevibacter* as the dominant methanogenic archaea in the rumen of cattle (Baca-González et al., 2020, p. 3). Here, promising results were achieved to implement for the first time a genetic toolbox for *M. boviskoreani* and *M. millerae*. For this purpose, a transformation strategy was used based on interdomain conjugation with *E. coli*. If this is confirmed by whole-genome sequencing, it would allow a new approach for identifying a specific and effective antigen against *Methanobrevibacter*, which would be a huge step towards immunize cattle. Besides this, it could be shown that *M. thaueri* and *M. boviskoreani* can be cultured and plated on media (DSM 1523 and 119) without rumenfluid

and the *Methanobrevibacter* are sensitive towards 20 µg/mL puromycin. In addition, first cellcounts per mL were determined (Figure A2) allowing first calculation of plating efficiency.

One problem that has been identified and must be resolved for future experiments is that the solvent DMSO has a clear inhibitory effect on the growth of *Methanob.* (see Section 4.1.5) due to its oxidative effect (Atcher & Alfonso, 2013). For chemicals that are poorly soluble in water, such as 8-Aza, which is needed for counterselection, an alternative solvent must be used.

As gets obvious here, the investigation on a possible vaccine for cattle against its methane producing microbiome is still in the beginning, so some time is needed until a possible vaccine could be available on the market. This means the mitigation strategy will not help to mitigate climate change in the next decade. Therefore, the best approach to reduce methane notably over the next years is to use the reduction potential, as for the USA is quit obvious with approx. (Figure 15), in the energy and waste sectors, which are, as shown for DEU in Figure 15, easier to modify with today's technics (Appelhans et al., 2025; IPCC, 2022b).

Nevertheless, this immunization strategy can be very useful in the long term for achieving the goal of net-zero emission (UNFCCC, 2015) within the agricultural sector, at least to some extent. This will even be more relevant, if taken into account, that the methane emission from natural sources such as permafrost will increase in the future due to the temperature rise (Schädel et al., 2026). But it must be noted here that even with a mitigation strategy that reduces emissions per head of cattle, it will still be necessary in the future to reduce the population to a sustainable size (Edelenbosch et al., 2024), which will be challenging with a growing demand for animal products (Appelhans et al., 2025; FAO, 2009). Here, the immunization or other strategies to reduce CH₄ production in cattle can allow a population size that can be socially accepted and politically feasibly.

Furthermore, the basic research conducted here on methane production by methanogenic archaea may be important not only for the development of a vaccine, but also for other mitigation strategies, such as food additives, and our general knowledge of methane production in natural sources.

Bastian sollte ich hier auch nochmal future steps of investigation nenne. Habe das ja eigtl schon im disscussionspart implementiert könnte hier aber nochmal zwei drei wichtige hervorheben. Finde den abschluss so aber eigtl ganz gut. wäre dann so was wie: Future steps for investigation are improving the transformation protokol for *Methanobrevibacter* and perform first genetic analyses. Furthermore, a intresting value to determine wit a gas chromatography would be how much methane the investigated strains produce. On the geograph-

ical site, the next step would be to perform the calculations for other countries as well, most interesting would be countries who are outside the ANNEX-I states. Furthermore, it should be investigated if the mitigation strategy has an impact on other emission sectors as well and interacts with them such as manure management or carbon sinks of pasture.

ACKNOWLEDGEMENTS

I would like to thank Prof. Molitor and Prof. Bastos for making it possible for me to complete a cooperative bachelor's thesis as well as for their excellent supervision. My thanks also go to Dr. Flaiz for his competent and friendly guidance in the lab, as well as his very helpful tips and advice along the way. Last but not least, I would like to thank the entire research group for their warm welcome during the time I worked on my bachelor's thesis, as well as my fellow bachelor's student, Linus S., for the great cooperation.

BIOCHEMICAL TERMS

β -sheet	A common secondary structure of proteins. It consists of β -strands arranged in parallel or antiparallel orientations. β -strands are illustrated as arrows. Another typical secondary structure is the α -helix.
16S-Sequencing	16S sequencing targets the 16s genes, which code for the 16S ribosomal RNA (rRNA). The 16S rRNA is a part of the prokaryotic ribosome. These 16-s base sequence is specific for the organism.
AlphaFold	Is a KI based software for prediction of 3-D structure of proteins. For the prediction it needs an amino acid sequence.
archaea	Archaea constitute one of the three major domains of life (bacteria, archaea, eukaryotes), and, like bacteria, they belong to the prokaryotes (Fritsche, 2024 , p. 3).
auxotrophic	Auxotrophic organism can not produce relevant bio-molecules for growth and surviving. Therefore, they must obtain these from their environment (Fritsche, 2024 , p. 65).
C-terminal end	The end of the amino acid sequence of a protein, where the carboxy group of the terminal amino acid has no covalent connection to another amino acid.
colony	In a microbiological context, a colony is defined as a clearly distinct cluster of cells that can be traced back to a single parent cell through cell division.

conjugation	Conjugation is the process of horizontal gen-transfer between a donor-cell and an acceptor-cell. The connection or "mating" between the cells is made by a pilus (also called "sex-pilus"), which allows the transport of the DNA. The conjugation can also happen between different species or domains. Needed for the conjugation is a plasmid that contains the gene for conjugation (the <i>tra</i> -region) and connection with a pilus (Fritsche, 2024 , p. 207).
glove-box	A sealed, airtight chamber system with built-in gloves that allow you to work from the outside while the internal atmosphere remains controlled (e.g. a anaerobic atmosphere).
in-vitro	Experiments are not performed in/ at the living organism, but in an artificial setting.
ORI	Origin of replication, is the region of the DNA, where the machinery responsible for replicating the entire genomic DNA first binds and begins replication.
PCR	The polymerase chain reaction is a in-vitro method to amplify a specific sequence of DNA. For this purpose, specific fitting primer has to be designed, that flank this DNA-sequence on both complementary DNA-strings..

phase-contrast microscope	Phase-contrast microscopy is based on the fact, that objects or medium not only changes the amplitude of light but also the phase of it. The phase-contrast microscope makes this phenomena visual for the human eye (Pawlizak, 2009).
plasmid	A small ring of double-stranded DNA. Occurs naturally in archaea and bacteria, but is also used for scientific purposes. Here often as a vector for a transformation.
Plating	Cultivate microorganism on a solid medium (contains a gelling agent like agar). Thereby is the plating the process how the organism get distributed on the plate / solid media. Different technics are possible like spreading or pouring (Fritsche, 2024 , p. 364).
pour plating	A plating technique in which the solution containing microorganisms is mixed with the agar-containing culture medium while it is still liquid (at about 45 °C). This mixture is then poured into a Petri dish, where it solidifies (Fritsche, 2024 , p. 364).
primer	Short nucleotide sequence that serves as a starting point for the polymerase to replicate the complementary DNA strand. For this purpose, the primer hybridizes to a specific sequence on the singlestranded-DNA (ss-DNA) template (Fritsche, 2024).
promotor	Region on DNA, which allows binding of relevant enzymes for the transcription of genes. So it is a essential region for gene expression.

restriction site	Restriction sites are a specific sequence of approx. 4 to 10 bp that are recognized by a specific restriction-enzyme. This cuts the double-stranded DNA at this site in a specific behavior.
ribosome	Ribosomes are a mix out ribosomal RNA (rRNA) and proteins. They play a central role in protein biosynthesis by catalyzing the translation of mRNA into an amino acid sequence.
spread plating	A plating technique in which the solution containing microorganisms is put on the solid agar-containing culture medium. The solution is then spread across the agar plate using a Dragalski spatula (Fritsche, 2024 , p. 364).
suicide plasmid	A plasmid that has no ORI and therefore can not be replicated in the cell except it gets integrated in the gDNA.
transformation	The process of getting a external DNA into the target organism and its expression. If the target organism is a animal eucaryotic cell it is called transfection.

GEOGRAPHICAL TERMS

ANNEX-I	ANNEX-I and Non-ANNEX-I countries is a classification of the UNFCCC. ANNEX-I are the OECD countries or countries with an economy in transition.
compound events	When two weather extremes occur at the same time or shortly after each other, so that they reinforce each other, as example a heatwave and droughts (IPCC, 2023b).
CRT	Common reporting table is a template for countries to report its emission of GHG fitting IPCC standards. The UNFCCC has obliged the ANNEX-I countries to publish this every year since 1990.
gross	In the context of climate change, the gross effect refers to the direct, physical influence of a greenhouse gas (such as methane) on the Earth's energy balance, considered in isolation. The net effect, by contrast, accounts for masking effects. For example, caused by co-emitted cooling agents, such as aerosols released during methane extraction, which can partially offset the gross warming contribution.

GWP	Global warming potential is a concept used to represent the relative impact of various GHGs on a uniform scale over a specific time period. It takes into account their effectiveness in causing radiative forcing as well as their atmospheric lifetime. CO ₂ serves as a reference, so that the effect of 1 g of greenhouse gas is converted to x g of CO ₂ eq.. The relevant time period is indicated as the number of years following the GWP designation (e. g., GWP20 refers to a 20-year time horizon).
planetary boundaries	Is a concept that uses the variability of values of the Holocene as a reference to evaluate thresholds for different processes to maintain a stable system on earth, where human mankind can definitely thrive. The nine main processes are "Climate change", "Biosphere integrity", "Land-system change", "Freshwater use", "Biogeochemical flows", "Ocean acidification", "Stratospheric ozone depletion", "Atmospheric aerosol loading" and "Novel entities" (Planetary Boundaries Science (PBScience), 2025).
radiative forcing	Is a concept that quantifies the change of the energy balance of the whole planet. The unit is W/m ² . It depends on many factors as e.g. aerosol content of the atmosphere, planetary albedo and the concentration of GHG (Irfan et al., 2024).

zone of an increasing risk "Refers to the stage when human activities push Earth beyond the Planetary Boundaries, entering a "Zone of Increasing Risk." In this zone, the further boundaries are exceeded, the greater the chance of causing serious damage, destabilizing key Earth system processes, and disrupting life-support functions" (Planetary Boundaries Science (PBScience), [2025](#)).

REFERENCES

- Apolinario, E. A., & Sowers, K. R. (1996). Plate colonization of *Methanococcus maripaludis* and *Methanosarcina thermophila* in a modified canning jar. *FEMS Microbiology Letters*, 145(1), 131–137. <https://doi.org/10.1111/j.1574-6968.1996.tb08567.x>
- Appelhans, J., Böttcher, C., Keßler, K., Mielke, C., Nowack, A., Purr, K., Schwetje, A., Sorg, D., & Tambke, J. (2025). Unterschätztes Treibhausgas Methan. Quellen, Wirkungen, Minderungsoptionen.
- Atcher, J., & Alfonso, I. (2013). The effect of DMSO in the aqueous thiol–disulphide dynamic covalent chemistry of model pseudopeptides. *RSC Advances*, 3(48), 25605–25608. <https://doi.org/10.1039/c3ra45811c>
- Baca-González, V., Asensio-Calavia, P., González-Acosta, S., Pérez de la Lastra, J. M., & Morales de la Nuez, A. (2020). Are Vaccines the Solution for Methane Emissions from Ruminants? A Systematic Review. *Vaccines*, 8(3), 460. <https://doi.org/10.3390/vaccines8030460>
- Boadi, D., Benchaar, C., Chiquette, J., & Massé, D. (2004). Mitigation strategies to reduce enteric methane emissions from dairy cows: Update review. *Canadian Journal of Animal Science*, 84(3), 319–335. <https://doi.org/10.4141/A03-109>
- C3S/ECMWF & WMO. (2026). *C3S-WMO European State of the Climate 2025*. <https://doi.org/10.24381/zy93-sb27>
- Capovilla, G., Castro, K. G., Ziegler, C. A., & Chisholm, S. W. (2025, September 21). *Transformation of plasmid DNA into Prochlorococcus via electroporation*. <https://doi.org/10.1101/2025.09.20.677525>
- CCAC. (n.d.). *Homepage | Global Methane Pledge*. Retrieved August 28, 2026, from <https://www.globalmethanepledge.org/>
- Edelenbosch, O. Y., Hof, A. F., van den Berg, M., de Boer, H. S., Chen, H.-H., Daioglou, V., Dekker, M. M., Doelman, J. C., den Elzen, M. G. J., Harmsen, M., Mikropoulos, S., van Sluisveld, M. A. E., Stehfest, E., Tagomori, I. S., van Zeist, W.-J., & van Vuuren, D. P. (2024). Reducing sectoral hard-to-abate emissions to limit reliance on carbon dioxide removal. *Nature Climate Change*, 14(7), 715–722. <https://doi.org/10.1038/s41558-024-02025-y>
- EPA. (2024). *Inventory of U.S. Greenhouse Gas Emissions and Sinks: 1990-2022* (EPA 430-R-24-004). U.S. Environmental Protection Agency. <https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks-1990-2022>

- European Commission. Joint Research Centre. (2025). *GHG emissions of all world countries: 2025*. Publications Office. Retrieved August 30, 2026, from <https://data.europa.eu/doi/10.2760/9816914>
- FAO (Ed.). (2009). *Livestock in the balance*. FAO.
- Fink, C., Beblawy, S., Enkerlin, A. M., Mühling, L., Angenent, L. T., & Molitor, B. (2021, April 20). *A shuttle-vector system allows heterologous gene expression in the thermophilic methanogen Methanothermobacter thermautotrophicus ΔH* . <https://doi.org/10.1101/2021.04.20.440605>
- Fritsche, O. (2024). *Mikrobiologie*. Springer Berlin Heidelberg. <https://doi.org/10.1007/978-3-662-70471-4>
- Garnett, L. M., & Eckard, R. J. (2024). Greenhouse-gas abatement on Australian dairy farms: What are the options? *Animal Production Science*, 64(16), AN24139. <https://doi.org/10.1071/AN24139>
- GML. (2025). *Annual Greenhouse Gas Index (AGGI) - NOAA Global Monitoring Laboratory*. Retrieved August 20, 2026, from <https://gml.noaa.gov/aggi/aggi.html>
- Hoedt, E. C., Cuív, P. Ó., Evans, P. N., Smith, W. J. M., McSweeney, C. S., Denman, S. E., & Morrison, M. (2016). Differences down-under: Alcohol-fueled methanogenesis by archaea present in Australian macropodids. *The ISME Journal*, 10(10), 2376–2388. <https://doi.org/10.1038/ismej.2016.41>
- International Monetary Fund. (n.d.). *World Economic Outlook (April 2026) - GDP, current prices*. IMF Data Mapper. Retrieved September 4, 2026, from <https://www.imf.org/external/datamapper/NGDPD@WEO>
- Ionita, M., & Nagavciuc, V. (2026). From droughts to hotter droughts: Europe's changing hydroclimate. *Journal of Hydrology: Regional Studies*, 66, 103684. <https://doi.org/10.1016/j.ejrh.2026.103684>
- IPCC. (2006a). *2006 IPCC guidelines for national greenhouse gas inventories* (H. S. Eggleston, Ed.). Institute for Global Environmental Strategies.
- IPCC. (2006b). Chapter 10: Emission from livestock and manure management. In H. Dong, J. Mangino, T. A. McAllister, J. L. Hatfield, D. E. Johnson, K. R. Lassey, M. Aparecida de Lima, & A. Romanovskaya (Eds.), *2006 IPCC Guidelines for National Greenhouse Gas Inventories*.
- IPCC. (2019). Chapter 10: Emission from livestock and manure management. In E. E. C. Buendia, K. Tanabe, A. Kranjc, B. Jamsranjav, M. Fukuda, S. Ngarize, A. Osako, Y.

- Pyrozhenko, P. Shermanau, & S. Federici (Eds.), *2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories* (Vol. 4).
- IPCC. (2022a). Agriculture, Forestry and Other Land Uses (AFOLU). In *Climate Change 2022 - Mitigation of Climate Change* (1st ed., pp. 747–860). Cambridge University Press. <https://doi.org/10.1017/9781009157926.009>
- IPCC. (2022b). *Climate Change 2022 – Impacts, Adaptation and Vulnerability* (H.-O. Pörtner, D. C. Roberts, M. Tignor, E. Poloczanska, K. Mintenbeck, A. Alegría, M. Craig, S. Langsdorf, S. Löschke, V. Möller, A. Okem, & B. Rama, Eds.; 1st ed.). Cambridge University Press. <https://doi.org/10.1017/9781009325844>
- IPCC. (2023a). *Climate Change 2021 – The Physical Science Basis: Working Group I Contribution to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change* (1st ed.). Cambridge University Press. <https://doi.org/10.1017/9781009157896>
- IPCC. (2023b). Annex I: Glossary. In H. Lee, IPCC, K. Calvin, D. Dasgupta, G. Krinner, A. Mukherji, P. W. Thorne, C. Trisos, J. Romero, P. Aldunce, K. Barrett, G. Blanco, W. W. Cheung, S. Connors, F. Denton, A. Diongue-Niang, D. Dodman, M. Garschagen, O. Geden, . . . N. Leprince-Ringuet (Eds.), *Climate Change 2023: Synthesis Report. Contribution of Working Groups I, II and III to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change* (pp. 119–130). <https://doi.org/10.59327/IPCC/AR6-9789291691647>
- Irfan, M., Musarat, M. A., Alaloul, W. S., & Ghufran, M. (2024). Chapter Eight - Radiative forcing on climate change: Assessing the effect of greenhouse gases on energy balance of Earth. In M. R. Rahimpour, M. A. Makarem, & M. Meshksar (Eds.), *Advances and Technology Development in Greenhouse Gases: Emission, Capture and Conversion* (pp. 137–167). Elsevier. <https://doi.org/10.1016/B978-0-443-19066-7.00012-6>
- Klein, M., Hilts, A. S., Fennessy, R. T., Trattig, N., Stehrer-Polášek, T., Rittmann, S. K.-M. R., & Fink, C. (2025). Markerless mutagenesis enables isoleucine biosynthesis solely from threonine in *Methanothermobacter marburgensis*. *Microbiology Spectrum*, 13(6), e03068–24. <https://doi.org/10.1128/spectrum.03068-24>
- Kopp, M., Irschik, H., Gross, F., Perlova, O., Sandmann, A., Gerth, K., & Müller, R. (2004). Critical variations of conjugational DNA transfer into secondary metabolite multiproducing *Sorangium cellulosum* strains So ce12 and So ce56: Development of a *mariner*-based transposon mutagenesis system. *Journal of Biotechnology*, 107(1), 29–40. <https://doi.org/10.1016/j.jbiotec.2003.09.013>

- Kryshtafovych, A., Schwede, T., Topf, M., Fidelis, K., & Moulton, J. (2021). Critical assessment of methods of protein structure prediction (CASP)—Round XIV. *Proteins: Structure, Function, and Bioinformatics*, 89(12), 1607–1617. <https://doi.org/10.1002/prot.26237>
- Lacalle, R. A., Pulido, D., Vara, J., Zaiacáin, M., & Jiménez, A. (1989). Molecular analysis of the pac gene encoding a puromycin N-acetyl transferase from *Streptomyces alboniger*. *Gene*, 79(2), 375–380. [https://doi.org/10.1016/0378-1119\(89\)90220-5](https://doi.org/10.1016/0378-1119(89)90220-5)
- Lambrecht, J., Cichocki, N., Hübschmann, T., Koch, C., Harms, H., & Müller, S. (2017). Flow cytometric quantification, sorting and sequencing of methanogenic archaea based on F420 autofluorescence. *Microbial Cell Factories*, 16(1), 180. <https://doi.org/10.1186/s12934-017-0793-7>
- Lee, J.-H., Kumar, S., Lee, G.-H., Chang, D.-H., Rhee, M.-S., Yoon, M.-H., & Kim, B.-C. (2013). *Methanobrevibacter boviskoreani* sp. nov., isolated from the rumen of Korean native cattle. *International Journal of Systematic and Evolutionary Microbiology*, 63, 4196–4201. <https://doi.org/10.1099/ijs.0.054056-0>
- Li, Y., Crouzet, L., Kelly, W. J., Reid, P., Leahy, S. C., & Attwood, G. T. (2023). *Methanobrevibacter boviskoreani* JH1T growth on alcohols allows development of a high throughput bioassay to detect methanogen inhibition. *Current Research in Microbial Sciences*, 4, 100189. <https://doi.org/10.1016/j.crmicr.2023.100189>
- LO - Laboroptik GmbH. (2026). *Zaehlkammer*. Retrieved August 6, 2026, from <http://www.zaehlkammer.de/deutsch/buerker.tuerk.html>
- Malyugina, S., Holik, S., & Horky, P. (2025). Mitigation strategies for methane emissions in ruminant livestock: A comprehensive review of current approaches and future perspectives. *Frontiers in Animal Science*, 6. <https://doi.org/10.3389/fanim.2025.1610376>
- Merck KGaA. (2026). *Cell Density measurement by OD600 Method*. Retrieved August 25, 2026, from <https://www.sigmaaldrich.com/DE/de/technical-documents/protocol/analytical-chemistry/photometry-and-reflectometry/cell-density-measurement-by-od600-method>
- MfE. (2026). *New Zealand's Greenhouse Gas Inventory 1990–2024*. Ministry for the Environment (MfE). Wellington.
- Miller, T. L., & Lin, C. (2002). Description of *Methanobrevibacter gottschalkii* sp. nov., *Methanobrevibacter thaueri* sp. nov., *Methanobrevibacter woesei* sp. nov. and *Methanobrevibacter wolinii* sp. nov.. *International Journal of Systematic and Evolutionary Microbiology*, 52(3), 819–822. <https://doi.org/10.1099/00207713-52-3-819>

- Mondorf, S., Deppenmeier, U., & Welte, C. (2012). A Novel Inducible Protein Production System and Neomycin Resistance as Selection Marker for *Methanosarcina mazei*. *Archaea*, 2012(1), 973743. <https://doi.org/10.1155/2012/973743>
- Morvan, B., Dore, J., Rieu-Lesme, F., Foucat, L., Fonty, G., & Gouet, P. (1994). Establishment of hydrogen-utilizing bacteria in the rumen of the newborn lamb. *FEMS Microbiology Letters*, 117(3), 249–256. <https://doi.org/10.1111/j.1574-6968.1994.tb06775.x>
- Moss, A. R., Jouany, J.-P., & Newbold, J. (2000). Methane production by ruminants: its contribution to global warming. *Annales de Zootechnie*, 49(3), 231–253. <https://doi.org/10.1051/animres:2000119>
- Mundra, I., & Lockley, A. (2024). Emergent methane mitigation and removal approaches: A review. *Atmospheric Environment: X*, 21, 100223. <https://doi.org/10.1016/j.aeaoa.2023.100223>
- Niebuhr, J., Fuss, R., & of Climate-Smart Agriculture, T. I. (2026). *Submission under the United Nations Framework Convention and the Paris Agreement – 2026 | National Inventory Report for the German Greenhouse Gas Inventory 1990-2024*. German Environment Agency.
- Olson, D. G., & Lynd, L. R. (2012). Transformation of *Clostridium Thermocellum* by Electroporation. In *Methods in Enzymology* (pp. 317–330, Vol. 510). Elsevier. <https://doi.org/10.1016/B978-0-12-415931-0.00017-3>
- Pawlizak, S. (2009). *Introduction: Phase Contrast Microscopy (PCM) - Soft Matter Physics Division - University of Leipzig*. Retrieved August 6, 2026, from <https://home.uni-leipzig.de/pwm/web/?section=introduction&page=phasecontrast>
- Planetary Boundaries Science (PBScience). (2025). *Planetary Health Check 2025: A Scientific Assessment of the State of the Planet* (N. H. Kitzmann, L. Caesar, B. Sakschewski, & J. Rockström, Eds.). Potsdam Institute for Climate Impact Research (PIK). Potsdam, Germany. <https://doi.org/10.48485/PIK.2025.017>
- Possot, O., Gernhardt, P., Klein, A., & Sibold, L. (1988). Analysis of drug resistance in the archaeobacterium *Methanococcus voltae* with respect to potential use in genetic engineering. *Applied and Environmental Microbiology*, 54(3), 734–740. <https://doi.org/10.1128/aem.54.3.734-740.1988>
- RKI. (2026, August 27). *Wochenbericht zur hitzebedingten Mortalität*. Retrieved September 2, 2026, from https://www.rki.de/DE/Themen/Gesundheit-und-Gesellschaft/Gesundheitliche-Einflussfaktoren-A-Z/H/Hitze/Bericht_Hitzemortalitaet.html

- Sanz, R., Aguado, R., Pedrosa, M. R., & Arnáiz, F. J. (2002). Simple and Selective Oxidation of Thiols to Disulfides with Dimethylsulfoxide Catalyzed by Dichlorodioxomolybdenum(VI). *Synthesis*, 2002(7), 856–858. <https://doi.org/10.1055/s-2002-28520>
- Saunois, M., Martinez, A., Poulter, B., Zhang, Z., Raymond, P. A., Regnier, P., Canadell, J. G., Jackson, R. B., Patra, P. K., Bousquet, P., Ciais, P., Dlugokencky, E. J., Lan, X., Allen, G. H., Bastviken, D., Beerling, D. J., Belikov, D. A., Blake, D. R., Castaldi, S., ... Zhuang, Q. (2025). Global Methane Budget 2000–2020. *Earth System Science Data*, 17(5), 1873–1958. <https://doi.org/10.5194/essd-17-1873-2025>
- Schädel, C., Gasser, T., Rogers, B. M., Treharne, R., Turetsky, M. R., Smith, T., MacDonald, E., & Natali, S. M. (2026). Permafrost and wildfire carbon emissions indicate need for additional action to keep Paris Agreement temperature goals within reach. *Communications Earth & Environment*, 7(1), 306. <https://doi.org/10.1038/s43247-026-03189-5>
- Schwalen, C. J., Hudson, G. A., Kille, B., & Mitchell, D. A. (2018). Bioinformatic Expansion and Discovery of Thiopeptide Antibiotics. *Journal of the American Chemical Society*, 140(30), 9494–9501. <https://doi.org/10.1021/jacs.8b03896>
- Smith, P., Reay, D., & Smith, J. (2021). Agricultural methane emissions and the potential for mitigation. *Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences*, 379(2210), 20200451. <https://doi.org/10.1098/rsta.2020.0451>
- Thoning, K., Dlugokencky, E., Lan, X., & NOAA Global Monitoring Laboratory. (2022). *Trends in globally-averaged CH₄, N₂O, and SF₆*. NOAA GML. <https://doi.org/10.15138/P8XG-AA10>
- Turetsky, M. R., Abbott, B. W., Jones, M. C., Anthony, K. W., Olefeldt, D., Schuur, E. A. G., Grosse, G., Kuhry, P., Hugelius, G., Koven, C., Lawrence, D. M., Gibson, C., Sannel, A. B. K., & McGuire, A. D. (2020). Carbon release through abrupt permafrost thaw. *Nature Geoscience*, 13(2), 138–143. <https://doi.org/10.1038/s41561-019-0526-0>
- UNFCCC. (2015). *The Paris Agreement*. Retrieved August 26, 2026, from <https://unfccc.int/process-and-meetings/the-paris-agreement>
- UNFCCC. (2026). *Common Reporting Tables*. Retrieved August 14, 2026, from https://www.unfccc.int/reports?search2=&search3=&items_per_page=10&f%5B0%5D=document_type%3A4593&order=name&sort=desc
- Wright, A. (2004). Reducing methane emissions in sheep by immunization against rumen methanogens. *Vaccine*, 22(29–30), 3976–3985. <https://doi.org/10.1016/j.vaccine.2004.03.053>

APPENDIX

A Figures



Figure A1: Phase-contrast microscope picture of *Methanobrevibacter boviskoreani* AbM4 culture precipitate at 1000 times magnification. *M. boviskoreani* was cultivated in DSM 1523.




Figure A2: Phase-contrast microscope picture of *Methanobrevibacter boviskoreani* AbM4 at 400 times magnification. One group square with its sixteen small squares of a Neubauer improve counting-chamber is shown.




Figure A3: Pour plating result of *Methanobrevibacter thaueri* CW^T DSM 119 (1 % agar). 100 μ l of a full-grown culture have been plated. Cultivated in a jar with H₂/CO₂ gas phase. No growth detected.




Figure A4: Time series of methane conversion factor (Ym), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for Germany. The data for dairy and non-dairy cattle is from the published CRT. The values for cattle is calculated as weighted mean of its subcategories, where the population-size is used as weight.




Figure A5: Time series of methane conversion factor (Ym), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for New Zealand. The data for dairy and non-dairy cattle is from the published CRT. The values for cattle is calculated as weighted mean of its subcategories, where the population-size is used as weight.




Figure A6: Time series of methane conversion factor (Ym), population-size, digestibility of food (DE) and gross energy intake (GE) of cattle and its subcategories dairy and non-dairy for United States of America. The data for dairy and non-dairy cattle is from the published CRT. The values for cattle are calculated as weighted mean of its subcategories, where the population-size is used as weight.

B Tables

Table B1: Composition for the **solution A** as a part of the DSM 1523 and DSM 119. Final concentration of defined chemicals are shown as well. The quantities listed are for 250 mL.

ingredient	quantity	concentration
KH ₂ PO ₄	12.50 g	367.40 mM
MgSO ₄ x 7 H ₂ O	10.00 g	162.28 mM
NaCl	10.00 g	684.46 mM
NH ₄ Cl	10.00 g	747.80 mM
Milli-Q H ₂ O	250.00 mL	–

Table B2: Composition for the **solution A** as a part of the DSM 1523. Final concentration of defined chemicals are shown as well. The quantities listed are for 275 mL. Solutions that have already been premixed are shown in bold. Composition of **Seven vitamins solution** is shown in Table B4.

ingredient	quantity	concentration
CaCl ₂	0.94 g	33.88 mM
Seven vitamins solution	25 mL	10 %
Milli-Q H ₂ O	250.00 mL	–

Table B3: Composition for the **trace element solution SL-10** as a part of the DSM 1523 and DSM 119. Final concentration of defined chemicals are shown as well. The quantities listed are for 1 L.

ingredient	quantity	concentration
HCl (12 %)	10.00 mL	1 %
FeCl ₂ x 4 H ₂ O	1.50 g	7.54 mM
ZnCl ₂	70.00 mg	513.61 µM
MnCl ₂ x 4 H ₂ O	100.00 mg	505.28 µM
H ₃ BO ₃	6.00 mg	97.04 µM
CoCl ₂ x 6 H ₂ O	190.00 mg	798.55 µM
CuCl ₂ x 2 H ₂ O	2.00 mg	11.73 µM
NiCl ₂ x 6 H ₂ O	24.00 mg	100.97 µM
Na ₂ MoO ₄ x 2 H ₂ O	36.00 mg	148.79 µM
Milli-Q H ₂ O	990.00 mL	–

Table B4: Composition for the **seven vitamins solution** as a part of the DSM 1523. Final concentration are shown as well for defined chemicals. The quantities listed are for 1 L.

ingredient	quantity	concentration
Vitamin B ₁₂	100.00 mg	73.78 µM
p-Aminobenzoic acid	80.00 mg	583.35 µM
D-(+)-biotin	20.00 mg	81.86 µM
Nicotinic acid	200.00 mg	1624.56 µM
Calcium pantothenate	100.00 mg	209.85 µM
Pyridoxine hydrochloride	300.00 mg	1458.86 µM
Thiamine-HCl x 2 H ₂ O	200.00 mg	535.76 µM
Milli-Q H ₂ O	1.00 L	–

Table B5: Composition for the **fatty acid mixture** as a part of the DSM 119. The quantities listed are for 1000 mL.

ingredient	quantity	concentration
Isobutyric acid	23.00 mL	2.3 %
DL-2-Methylbutyric acid	27.00 mL	2.7 %
Valeric acid	27.00 mL	2.7 %
Isovaleric acid	27.00 mL	2.7 %
Milli-Q H ₂ O	896.00 mL	–

Table B6: Composition for the **FeSO₄ x 7 H₂O solution (0.1 % w/v)** as a part of the DSM 119. Final concentration was calculated as well. The quantities listed are for 1000 mL 0.1N H₂SO₄ solution.

ingredient	quantity	concentration
FeSO ₄ x 7 H ₂ O	1.00 g	3.60 mM
H ₂ SO ₄ (0.1 N)	1000.00 mL	–

Table B7: Primerlist of the primers used in this bachelor thesis. Besides the name of the primer, also the sequence (5' to 3') is given and its annealing temperature (T_a) with the Q5- and OneTaq-DNA-polymerase.

No.	name	Sequence	T_a Q5 (°C)	T_a OneTaq (°C)
1	27F	AGAGTTTGATCATGGCTCAG	–	45.0
2	1510R	GGTTACCTTGTTACGACTT	–	45.0
17	FW_PhmtB-FseI-NEB	TCAACTTGCCCACTGGCCGGCCCCCATGAACCAACCGATG	61.7	–
22	Met86F	GCTCAGTAACACGTGG	61.0	46.0
23	Met1340R	CGGTGTGTGCAAGGAG	61.0	46.0
38	FW-screen-BBpMr	TTGGA CTCAAGACGATAGTT	46.0	–
39	RV-screen-BBpMr	GGCAGTACACCTTGATAGG	46.0	–
48	FW-Mthau-LHA-hpt_NEB	CATCGGTTGGTTCATGGGGGCGCGCCTTCAGCCTTCTCGATCAATG	58.8	–
≤ 49	RV-Mthau-LHA-hpt_NEB	CCAAATCCATCATAGTACTCACACAAAAATTATTAAAC	58.8	–
50	FW-Mthau-RHA-hpt_NEB	GAGTACTATGATGGATTTGGATAAGGTAATC	57.2	–
51	RV-Mthau-RHA-hpt_NEB	CAGGAAACAGCTATGACCGCGGCCGCTGTTTAAGACTATTTCCAATTCC	57.2	–
52	FW-Mb-LHA-hpt_NEB	CATCGGTTGGTTCATGGGGGCGCGCCGATTTCCAATTCTTG GGG	56.1	–
53	RV-Mb-LHA-hpt_NEB	GAAAATTATGTAATCCTAAAGACTATCTAAATTTAAC	56.1	–
54	FW-Mb-RHA-hpt_NEB	TTTAGGATTACATAATTTTCCTCTTTAATTTAAATTAAAAATATAATTTTAAAAATTG	60.4	–
55	RV-Mb-RHA-hpt_NEB	CAGGAAACAGCTATGACCGCGGCCGCGGAACCAATATCGGTAGC	60.4	–
63	RV_Mthau_pac_opt_Smal_NEB	GGGGTCGGCGGGGCGCCCGGGTTAGGCACCTGGTTTTCTTG	63.4	–
71	RV_Mb_pac_opt_Smal_NEB	GGGGTCGGCGGGGCGCCCGGGTTATGCTCCTGGTTTTCTGG	62.9	–

Table B8: Counted cells for *Methanobrevibacter wolinii* SH^T with an OD600 of 0.387. Cells were counted with a phase-contrast microscope and a Bürker counting chamber at 400x magnification. Per chamber filling four square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:20 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	$\bar{x}$ cellnumber
1	138	159	226	233	189
2	260	271	293	265	272.25
3	180	197	216	188	195.25
4	207	191	211	227	209

Table B9: Counted cells for *Methanobrevibacter wolinii* SH^T with an OD600 of 0.396. Cells were counted with a phase-contrast microscope and a Neubauer improved counting chamber at 400x magnification. Per chamber filling four large-square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:20 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	$\bar{x}$ cellnumber
1	177	239	263	254	233.25
2	246	241	267	208	240.5
3	175	176	161	221	183.25
4	217	185	205	180	196.75

Table B10: Counted cells for *Methanobrevibacter thaueri* CW^T with an OD600 of 0.235. Cells were counted with a phase-contrast microscope and a Neubauer improved counting chamber at 400x magnification. Per chamber filling four large-square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:10 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	$\bar{x}$ cellnumber
1	189	232	250	265	234
2	237	209	224	263	233.25
3	186	253	230	237	226.5
4	146	187	216	262	202.75

Table B11: Counted cells for *Methanobrevibacter thaueri* CW^T with an OD600 of 0.116. Cells were counted with a phase-contrast microscope and a Neubauer improved counting chamber at 400x magnification. Per chamber filling four large-square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:10 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	$\bar{x}$ cellnumber
1	255	181	189	171	199
2	127	92	131	193	135.75
3	110	136	153	109	127
4	127	93	109	156	121.25

Table B12: Counted cells for *Methanobrevibacter millerae* SM9 with an OD600 of 0.378. Cells were counted with a phase-contrast microscope and a Neubauer improved counting chamber at 400x magnification. Per chamber filling four large-square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:20 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	Sqr. 5	$\bar{x}$ cellnumber
1	186	175	173	156	220	182
2	118	204				161
3	211	178	232	211	184	203.2
4	128	128	201	204	160	164.2

Table B13: Counted cells for *Methanobrevibacter boviskoreani* AbM4 with an OD600 of 0.287. Cells were counted with a phase-contrast microscope and a Neubauer improved counting chamber at 400x magnification. Per chamber filling four large-square (Sqr.) with a volume of $4 \cdot 10^{-6}$ mL were counted. The arithmetic mean ($\bar{x}$ cellnumber) per chamber filling was calculated. The culture was diluted 1:20 in DSM 1523 before counting.

chamber	Sqr. 1	Sqr. 2	Sqr. 3	Sqr. 4	$\bar{x}$ cellnumber
1	123	162	166	170	155.25
2	162	228	205	242	209.25
3	170	128	137	213	162
4	187	174	263	237	215.25

Table B14: The total average of counted cells ($\bar{x}$ cellnumber) for each *Methanobrevibacter* (*Methanob.*) culture with corresponding OD600. Counting was done with a phase-contrast microscope and a Bürker or Neubauer improved counting chamber at 400x magnification. $\bar{x}$ cellnumber was calculated as arithmetic mean of shown cellcounts in tab. B8 through B13. The dilution factor takes into account the dilution of the culture being counted.

culture	OD600	Dilution factor	$\bar{x}$ cellnumber
M. wolinii	0.387	20	216.375
M. wolinii	0.396	20	213.438
M. thaueri	0.235	10	224.125
M. thaueri	0.116	10	145.750
M. millerae	0.378	20	177.600
M. boviskoreani	0.287	20	185.438

Table B15: In-silico produced suicide plasmid constructs for transformation of *Methanobrevibacter thaueri* CW^T and *Methanobrevibacter boviskoreani* AbM4 via conjugation. The listed plasmids follow the general structure shown in Figure 2 and were created in SnapGene. The name of each plasmid is derived from the organism for which it possesses the appropriate homology arms (pMt for *M. thaueri* and pMb for *M. boviskoreani*) and the four named columns, where ORI refers to *Methanob.* in this case and the promotor for the *pac*. *pac_org* is the *pac* with the original sequence derived from *Streptomyces alboniger*, *pac_opt* is the codon optimized version for the affected organism. The size of the constructed is given in bp as well.

name	ORI	promoter	pac	extra feature	size (bp)
pMt_0231_hpt	/ (0)	hmtB (2)	pac_opt (3)	hpt (1)	6145
pMt_0331_hpt	/ (0)	PglnA (3)	pac_opt (3)	hpt (1)	6254
pMt_0241_hpt	/ (0)	hmtB (2)	pac_org (4)	hpt (1)	6145
pMt_0341_hpt	/ (0)	PglnA (3)	pac_org (4)	hpt (1)	6254
pMb_0231_hpt	/ (0)	hmtB (2)	pac_opt (3)	hpt (1)	6214
pMb_0331_hpt	/ (0)	PglnA (3)	pac_opt (3)	hpt (1)	6323

Table B16: Preparation of the conjugation for the transformation of *Methanobrevibacter thaueri* CW^T, *Methanobrevibacter boviskoreani* AbM4, and *Methanobrevibacter millerae* SM9. Two DAP-auxotrophic *Escherichia coli* strains were used for conjugation, WM6026 and WM6029. The final OD600 was measured as a 1:10 dilution with LB-media before the Plating with *Methanobrevibacter*. The *E. coli* for *M. thaueri* contained the plasmid pMt_0231_hpt, for *M. boviskoreani* the plasmid pMb_0231_hpt, and for *M. millerae* the plasmid pMm_0231_hpt. Cultures marked with an asterisk showed visible growth for the first time on the day they were used for conjugation. Preparations from the same *Methanobrevibacter* pre-culture share the same first number (No.). Preparations from the same plate are distinguished by the letters A and B. Before being transferred to a 10 mL DSM 1523 medium containing 200 µg/mL cycloserin (Cyc-Se.) and no DAP, the strains *Methanobrevibacter* and *E. coli* were incubated overnight on agar plates containing 10 mM MgSO₄, 5 mM CaCl₂, and 0.1 mM DAP overnight in a jar (headspace with H₂/CO₂ mix). t_P is the time that elapsed during recovery before puromycin (final concentration of 20 µg/mL) was added. The time from this point until the first transfer of the culture to a new DSM 1523 medium with the same concentrations of Cyc-Se. and Puro was measured and denoted as t_{1,t}. t_{2,t} then indicates the number of days that elapsed until the second transfer. The samples marked in red are those that showed visible growth in one of the transferred cultures and were collected for sequencing.

No.	<i>Methanobrevibacter</i>	<i>E. coli</i> (OD600)	t _P [h]	t _{1,t} [h]	t _{2,t} [d]
1.6A	<i>M. thaueri</i>	WM6026 (1.02)	5	17	4
1.6B			19.5	2.5	
1.9A		WM6029 (1.30)	5	17	
1.9B			19.5	2.5	
2.6A	<i>M. boviskoreani</i>	WM6026 (1.22)	5	17	4
2.6B			19.5	2.5	
3.6A			5	17	
3.6B			19.5	2.5	
2.9A		WM6029 (1.15)	5	17	
2.9B			19.5	2.5	
3.9A			5	17	
3.9B			19.5	2.5	
4.6A	<i>M. millerae</i> *	WM6026 (1.24)	5	17	4
4.6B			19.5	2.5	
5.6A			5	17	
5.6B			19.5	2.5	
4.9A		WM6029 (1.59)	5	17	
4.9B			19.5	2.5	
5.9A			5	17	
5.9B			19.5	2.5	
6.6A	<i>M. boviskoreani</i> *	WM6026 (1.79)	4.5	0.5	4
6.6B			21	0.5	3
7.6A			4.5	0.5	4
7.6B			21	0.5	3
6.9A		WM6029 (0.60)	4.5	0.5	4
6.9B			21	0.5	3
7.9A			4.5	0.5	4
7.9B			21	0.5	3

Table B17: Lists saved CH₄ for five scenarios of different success in shifting the microbiom from methanogen towards non-methanogen (10, 20, 30, 40 and 50 %). It was calculated an average for the decade 2010 to 2019 for the three countries Germany (DEU), New Zealand (NZL), United States of America (USA). The CO₂ eq. was calculated for the GWP20 and GWP100 with factors taken from IPCC (2023a, Table 7.15, Chapter 7) (79.7 for GWP20 and 27 for GWP100)

country	red.-scenario	CH ₄ [Tg]	GWP20 [Tg CO ₂ eq.]	GWP100 [Tg CO ₂ eq.]
DEU	10	0.104	8.321	2.819
DEU	20	0.207	16.460	5.576
DEU	30	0.306	24.424	8.274
DEU	40	0.404	32.220	10.915
DEU	50	0.500	39.853	13.501
NZL	10	0.088	7.032	2.382
NZL	20	0.174	13.906	4.711
NZL	30	0.259	20.628	6.988
NZL	40	0.341	27.204	9.216
NZL	50	0.422	33.639	11.396
USA	10	0.750	59.739	20.238
USA	20	1.480	117.953	39.959
USA	30	2.192	174.707	59.186
USA	40	2.887	230.061	77.938
USA	50	3.564	284.071	96.235

Table B18: Listed linear models for predicting relevant values for calculating 2030 CH₄ emission of **Germany**. The relevant indicators are total methane emission without cattle enteric fermentation (EnterFe) and Ym (methane conversion factor), DE (digestibility), NE_x (net energy intake), population size for dairy cattle (DC) and non-dairy cattle (NDC). For fitting the linear models three different time periods were used (the last 5, 10 or 15 years of the data set). The fitted value is thereby depended on the time. Besides the equation, the R² is given as well. R² for the 15-year model of "NDC YM [%]" turns zero because no change is predicted.

time sample	fitted value	equation	R ²
5	total CH ₄ without cattle EnterFe [kt]	$y = -6.25 \cdot x + 13677.282$	0.070
5	DC population size [1000s]	$y = -78.386 \cdot x + 162269.508$	0.956
5	DC Ym [%]	$y = -0.023 \cdot x + 52.062$	0.712
5	DC DE [%]	$y = 0.063 \cdot x - 51.879$	0.735
5	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 1.868 \cdot x - 3630.669$	0.720
5	NDC population size [1000s]	$y = -110.076 \cdot x + 229727.445$	0.893
5	NDC Ym [%]	$y = 0.005 \cdot x - 4.499$	0.821
5	NDC DE [%]	$y = -0.035 \cdot x + 144.304$	0.891
5	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.129 \cdot x - 215.365$	0.888
10	total CH ₄ without cattle EnterFe [kt]	$y = -36.946 \cdot x + 75747.569$	0.792
10	DC population size [1000s]	$y = -76.559 \cdot x + 158578.922$	0.988
10	DC Ym [%]	$y = -0.024 \cdot x + 55.219$	0.946
10	DC DE [%]	$y = 0.057 \cdot x - 40.026$	0.932
10	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 1.941 \cdot x - 3778.256$	0.946
10	NDC population size [1000s]	$y = -168.698 \cdot x + 348278.384$	0.974
10	NDC Ym [%]	$y = 0.002 \cdot x + 2.939$	0.483
10	NDC DE [%]	$y = -0.016 \cdot x + 106.264$	0.749
10	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.209 \cdot x - 377.797$	0.957
15	total CH ₄ without cattle EnterFe [kt]	$y = -40.092 \cdot x + 82103.312$	0.934
15	DC population size [1000s]	$y = -44.459 \cdot x + 93727.349$	0.767
15	DC Ym [%]	$y = -0.023 \cdot x + 52.942$	0.977
15	DC DE [%]	$y = 0.032 \cdot x + 10.375$	0.716
15	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 1.532 \cdot x - 2951.872$	0.940
15	NDC population size [1000s]	$y = -125.537 \cdot x + 261079.881$	0.917
15	NDC Ym [%]	$y = 0 \cdot x + 6.57$	0.000
15	NDC DE [%]	$y = -0.014 \cdot x + 102.431$	0.852
15	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.144 \cdot x - 246.555$	0.863

Table B19: Listed linear models for predicting relevant values for calculating 2030 CH₄ emission of **New Zealand**. The relevant indicators are total methane emission without cattle enteric fermentation (EnterFe) and Ym (methane conversion factor), DE (digestibility), NE_x (net energy intake), population size for dairy cattle (DC) and non-dairy cattle (NDC). For fitting the linear models three different time periods were used (the last 5, 10 or 15 years of the data set). The fitted value is thereby depended on the time. Besides the equation, the R² is given as well. R² is NA for indicators where the variance of the values is zero. In addition there are two zero values because of rounding, first the slope of the 15-year model for "NDC DE [%]" and the R² for the 15-year model of "NDC population size [1000s]".

time sample	fitted value	equation	R ²
5	total CH ₄ without cattle EnterFe [kt]	$y = -12.753 \cdot x + 26300.235$	0.997
5	DC population size [1000s]	$y = -102.756 \cdot x + 213780.671$	0.887
5	DC Ym [%]	$y = 0 \cdot x + 6.5$	NA
5	DC DE [%]	$y = 0.011 \cdot x + 54.263$	0.570
5	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.715 \cdot x - 1352.955$	0.797
5	NDC population size [1000s]	$y = -71.703 \cdot x + 148784.07$	0.732
5	NDC Ym [%]	$y = 0 \cdot x + 6.5$	NA
5	NDC DE [%]	$y = 0 \cdot x + 70.346$	NA
5	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.937 \cdot x - 1835.457$	0.852
10	total CH ₄ without cattle EnterFe [kt]	$y = -10.058 \cdot x + 20851.018$	0.978
10	DC population size [1000s]	$y = -88.716 \cdot x + 185394.664$	0.930
10	DC Ym [%]	$y = 0 \cdot x + 6.5$	NA
10	DC DE [%]	$y = -0.007 \cdot x + 90.206$	0.305
10	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.906 \cdot x - 1740.452$	0.895
10	NDC population size [1000s]	$y = 22.947 \cdot x - 42611.147$	0.211
10	NDC Ym [%]	$y = 0 \cdot x + 6.5$	NA
10	NDC DE [%]	$y = 0 \cdot x + 70.346$	NA
10	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.508 \cdot x - 968.768$	0.773
15	total CH ₄ without cattle EnterFe [kt]	$y = -9.839 \cdot x + 20408.364$	0.992
15	DC population size [1000s]	$y = -29.407 \cdot x + 65583.652$	0.219
15	DC Ym [%]	$y = 0 \cdot x + 6.5$	NA
15	DC DE [%]	$y = 0.021 \cdot x + 33.254$	0.469
15	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 1.019 \cdot x - 1969.163$	0.966
15	NDC population size [1000s]	$y = -0.097 \cdot x + 3942.39$	0.000
15	NDC Ym [%]	$y = 0 \cdot x + 6.5$	NA
15	NDC DE [%]	$y = 0 \cdot x + 71.161$	0.481
15	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.105 \cdot x - 153.685$	0.096

Table B20: Listed linear models for predicting relevant values for calculating 2030 CH₄ emission of the **USA**. The relevant indicators are total methane emission without cattle enteric fermentation (EnterFe) and Ym (methane conversion factor), DE (digestibility), NE_x (net energy intake), population size for dairy cattle (DC) and non-dairy cattle (NDC). For fitting the linear models three different time periods were used (the last 5, 10 or 15 years of the data set). The fitted value is thereby depended on the time. Besides the equation, the R² is given as well. Slope of the 15-year model for "DC DE [%]" is zero due to rounding issues.

time sample	fitted value	equation	R ²
5	total CH ₄ without cattle EnterFe [kt]	$y = -529.671 \cdot x + 1091556.297$	0.989
5	DC population size [1000s]	$y = -78.221 \cdot x + 176838.967$	0.789
5	DC Ym [%]	$y = -0.001 \cdot x + 8.017$	0.704
5	DC DE [%]	$y = 0.006 \cdot x + 53.297$	0.845
5	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.736 \cdot x - 1400.748$	0.977
5	NDC population size [1000s]	$y = -526.204 \cdot x + 1143925.596$	0.765
5	NDC Ym [%]	$y = -0.01 \cdot x + 27.096$	0.960
5	NDC DE [%]	$y = 0.081 \cdot x - 96.049$	0.952
5	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.173 \cdot x - 295.476$	0.921
10	total CH ₄ without cattle EnterFe [kt]	$y = -245.886 \cdot x + 518212.392$	0.753
10	DC population size [1000s]	$y = 21.479 \cdot x - 24555.96$	0.144
10	DC Ym [%]	$y = -0.003 \cdot x + 12.927$	0.802
10	DC DE [%]	$y = 0.002 \cdot x + 62.028$	0.293
10	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.671 \cdot x - 1269.793$	0.990
10	NDC population size [1000s]	$y = 638.685 \cdot x - 1209266.975$	0.544
10	NDC Ym [%]	$y = -0.006 \cdot x + 19.106$	0.787
10	NDC DE [%]	$y = 0.049 \cdot x - 32.878$	0.820
10	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.113 \cdot x - 173.444$	0.838
15	total CH ₄ without cattle EnterFe [kt]	$y = -236.704 \cdot x + 499649.489$	0.876
15	DC population size [1000s]	$y = 35.307 \cdot x - 52471.673$	0.536
15	DC Ym [%]	$y = -0.005 \cdot x + 16.261$	0.916
15	DC DE [%]	$y = 0 \cdot x + 65.618$	0.011
15	DC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.617 \cdot x - 1159.782$	0.993
15	NDC population size [1000s]	$y = 104.563 \cdot x - 131253.734$	0.040
15	NDC Ym [%]	$y = -0.006 \cdot x + 17.665$	0.876
15	NDC DE [%]	$y = 0.043 \cdot x - 19.257$	0.890
15	NDC NE _x [MJ head ⁻¹ day ⁻¹]	$y = 0.106 \cdot x - 158.969$	0.915

DECLARATION

I hereby declare that I have written the present thesis independently and without the use of sources other than those named. Artificial intelligence (AI) tools were used exclusively for language editing and programming assistance in R and $\text{\LaTeX}$, and not for the generation of scientific content or analysis. Sentences or parts of sentences quoted literally are marked as such; other references with regard to the statement and scope are indicated by full details of the publications concerned. The thesis in the same or similar form has not been submitted to any examination body and has not been published. This thesis was not yet, even in part, used in another examination or as a course performance. Furthermore, I declare that the submitted written (bound) copies of the present thesis and the version submitted on a data carrier are consistent with each other in contents.

Place, date

Signature